



Department of Energy
Richland Operations Office
P.O. Box 550
Richland, Washington 99352

13-AMRP-0077

JAN 04 2013


Ms. J. A. Hedges, Program Manager
Nuclear Waste Program
State of Washington
Department of Ecology
3100 Port of Benton Blvd.
Richland, Washington 99354

Dear Ms. Hedges:

TRANSMITTAL OF APPROVED WASTE SITE RECLASSIFICATION FORM NO. 2012-079
AND SUPPORTING DOCUMENTATION FOR THE 100-N-25, FRENCH DRAIN 1 LIQUID
WASTE SITE, REVISION 0

Attached for your use is the approved Waste Site Reclassification Form No. 2012-079,
and supporting "Remaining Sites Verification Package for the 100-N-25, French Drain 1 Liquid
Waste Site," Rev. 0. If you have questions, please contact me or your staff may contact
Joanne Chance, of my staff, at (509) 376-0811.

Sincerely,


Mark S. French, Federal Project Director
for the River Corridor Closure Project

AMRP:JCC

cc w/attach:
N. M. Menard, Ecology
Administrative Record, H6-08

cc w/o attach:
R. D. Cantwell, WCH
S. L. Feaster, WCH
T. Q. Howell, WCH
D. L. Plung, WCH
J. P. Shearer, CHPRC

WASTE SITE RECLASSIFICATION FORM

Operable Unit: 100-NR-1

Control No.: 2012-079

Waste Site Code(s)/Subsite Code(s): 100-N-25

Reclassification Category: Interim ☒ Final ☐

Reclassification Status: Closed Out ☒ No Action ☐ Rejected ☐
RCRA Postclosure ☐ Consolidated ☐ None ☐

Approvals Needed: DOE ☒ Ecology ☒ EPA ☐

Description of current waste site condition:

The 100-N-25, French Drain 1 Liquid Waste Site was identified as a 100-NR-1 Operable Unit waste site requiring remediation in the *Interim Action Record of Decision for the 100-NR-1 and 100-NR-2 Operable Units, Hanford Site, Benton County, Washington* (100-N Area ROD) (EPA 1999).

The location of the waste site is approximately 82 m (270 ft) south of the location of the 116-N-2 waste site. The purpose of the french drain is unknown; however, the nearest structure was the 1105-N Administrative Office Trailer, which existed from 1975 to 1986. There were no above or below grade pipelines found to have led to the drain; therefore, it was speculated that the drain was used for water runoff from the nearby office trailer roof or condensate from an air conditioning unit.

Remedial action at the 100-N-25 waste site was performed between March 27 and 29, 2012. The waste site was excavated to an approximate depth of 4 m (13 ft) below ground surface resulting in approximately 333 bank cubic meters (436 bank cubic yards) of soil removed for disposal at the Environmental Restoration Disposal Facility (ERDF). There was no evidence of a french drain found during remediation.

Remediation, verification sampling, and a comparison of residual contaminant concentrations against cleanup levels have been performed in accordance with remedial action objectives and remedial action goals (RAGS) established by the *Interim Action Record of Decision for the 100-NR-1 and 100-NR-2 Operable Units, Hanford Site, Benton County, Washington* (100-N Area ROD), U.S. Environmental Protection Agency, Region 10, Seattle, Washington (EPA 1999). The selected remedy involved (1) excavating the site to the extent required to meet specified soil cleanup levels, (2) disposing of contaminated excavation materials at the ERDF, (3) demonstrating through verification sampling that cleanup goals have been achieved, and (4) proposing the site for reclassification as Interim Closed Out.

Basis for reclassification:

Cleanup verification sampling results were evaluated in comparison to the RAGs. In accordance with this evaluation, the verification sampling results supports a reclassification of the 100-N-25 waste site to Interim Closed Out. The current site conditions achieve the RAGs established by the 100-N Area ROD (EPA 1999). The evaluation (which may include fate-and-transport modeling) of all data collected from the waste site resulted in a determination that residual contaminant concentrations do not preclude any future uses (as bounded by the rural-residential scenario) and allow for unrestricted use of shallow-zone soils (i.e., surface to 4.6 m [15 ft] deep). The results from the base of the excavation also demonstrate that residual contaminant concentrations are protective of groundwater and the Columbia River. Contamination above direct exposure levels was not observed in shallow zone soils and is concluded to not exist in deep zone soils; therefore, institutional controls to prevent uncontrolled drilling or excavation into the deep zone soil are not required. The basis for reclassification is described in detail in the *Remaining Sites Verification Package for the 100-N-25, French Drain 1 Liquid Waste Site* (attached).

WASTE SITE RECLASSIFICATION FORM

Operable Unit: 100-NR-1

Control No.: 2012-079

Waste Site Code(s)/Subsite Code(s): 100-N-25

Regulator comments:

Approval of this Waste Site Reclassification Form documents the regulator's agreement that the 100-N-25 waste site qualifies for "Interim Closed Out" under this Interim Action ROD. In addition, the lead regulator has evaluated the data for this site against WAC 173-340 (2007) cleanup levels for direct contact, groundwater protection, and river protection. This evaluation is documented in the letter transmitting the lead regulator's approval of the site's reclassification to "Interim Closed Out."

Waste Site Controls:

Engineered Controls: ☐ Yes ☒ No Institutional Controls: ☐ Yes ☒ No O&M Requirements: ☐ Yes ☒ No

If any of the Waste Site Controls are checked Yes, specify control requirements including reference to the Record of Decision, TSD Closure Letter, or other relevant documents:

J. P. Neath

DOE Federal Project Director (printed)

Signature

Date

N. Menard

Ecology Project Manager (printed)

Signature

Date

N/A

EPA Project Manager (printed)

Signature

Date

**REMAINING SITES VERIFICATION PACKAGE FOR THE
100-N-25, FRENCH DRAIN 1 LIQUID WASTE SITE**

Attachment to Waste Site Reclassification Form 2012-079

December 2012

REMAINING SITES VERIFICATION PACKAGE FOR THE 100-N-25, FRENCH DRAIN 1 LIQUID WASTE SITE

EXECUTIVE SUMMARY

The 100-N-25, French Drain 1 Liquid Waste Site, part of the 100-NR-1 Operable Unit, is located approximately 82 m (270 ft) south of the location of the 116-N-2 waste site. The purpose of the french drain is unknown; however, the nearest structure was the 1105-N Administrative Office Trailer, which existed from 1975 to 1986. No above- or below-grade pipelines were found to have led to the drain; therefore, it was speculated that the drain was used for water runoff from the nearby office trailer roof or condensate from an air conditioning unit.

Remediation of the 100-N-25 waste site was performed between March 27 and 29, 2012. The waste site was excavated to an approximate depth of 4 m (13 ft) below ground surface resulting in approximately 333 bank cubic meters (436 bank cubic yards) of soil and debris being removed and disposed at the Environmental Restoration Disposal Facility. There was no evidence of a french drain found during remediation. No overburden soil was stockpiled to be used as backfill.

Verification sampling was conducted on July 24, 2012. A summary of the cleanup evaluation for the soil sampling results against the applicable remedial action goals (RAGs) is presented in Table ES-1. The results of the verification sampling were used to make reclassification decisions for the 100-N-25 waste site in accordance with the TPA-MP-14 procedure in the *Tri-Party Agreement Handbook Management Procedures* (DOE-RL 2011).

In accordance with this evaluation, the verification sampling results and modeling support a reclassification of this site to Interim Closed Out. The current site conditions achieve the remedial action objectives (RAOs) and the corresponding RAGs established in the *Remedial Design Report/Remedial Action Work Plan for the 100-N Area* (DOE-RL 2006b), and the *Interim Action Record of Decision for the 100-NR-1 and 100-NR-2 Operable Units, Hanford Site, Benton County, Washington* (100-N Area ROD) (EPA 1999). These results show that residual soil concentrations support future land uses that can be represented (or bounded) by a rural-residential scenario. The sample and modeling results also demonstrate that residual contaminant concentrations support unrestricted future use of shallow zone soil (i.e., surface to 4.6 m [15 ft]), and contaminant levels remaining in the soil are protective of groundwater and the Columbia River. The 100-N-25 waste site was excavated to a depth of approximately 4 m (13 ft) below ground surface. Contamination above direct exposure levels was not observed in shallow zone soils and is concluded to not exist in deep zone soils; therefore, institutional controls to prevent uncontrolled drilling or excavation into the deep zone of the site are not required.

Table ES-1. Summary of Remedial Action Goals for the 100-N-25 Waste Site.

Regulatory Requirement	Remedial Action Goals	Results	Remedial Action Objectives Attained?
Direct Exposure – Radionuclides	Attain dose rate of <15 mrem/yr above background over 1,000 years.	Radionuclides were not identified as COPCs for this site.	NA
Direct Exposure – Nonradionuclides	Attain individual COPC RAGs.	All individual COPC concentrations are below the direct exposure criteria.	Yes
Risk Requirements – Nonradionuclides	Attain a hazard quotient of <1 for all individual noncarcinogens.	The hazard quotients for individual nonradionuclide COPCs are <1.	Yes
	Attain a cumulative hazard quotient of <1 for noncarcinogens.	The cumulative hazard quotient for all sampling areas (1.9×10^{-3}) is <1.	
	Attain an excess cancer risk of <1 x 10 ⁻⁶ for individual carcinogens.	The excess cancer risk for individual carcinogens is <1 x 10 ⁻⁶ .	
	Attain a cumulative excess cancer risk of <1 x 10 ⁻⁵ for carcinogens.	The total excess cancer risk (6.2×10^{-7}) is <1 x 10 ⁻⁵ .	
Groundwater/River Protection – Radionuclides	Attain single COPC groundwater and river RAGs.	Radionuclides were not identified as COPCs for this site.	NA
	Attain National Primary Drinking Water Regulations ^a : 4 mrem/yr (beta/gamma) dose standard to target receptor/organ.		
	Meet drinking water standards for alpha emitters: the more stringent of 15 pCi/L MCL or 1/25 th of the derived concentration guide for DOE Order 5400.5 ^b .		
	Meet total uranium standard of 30 µg/L (21.2 pCi/L) ^c .		
Groundwater/River Protection – Nonradionuclides	Attain individual nonradionuclide groundwater and Columbia River cleanup requirements.	Residual concentrations of benzo(a)anthracene, benzo(a)pyrene, benzo(b)fluoranthene, benzo(k)fluoranthene, and indeno(1,2,3-cd)pyrene exceed soil RAGs for groundwater and/or river protection. However, based on RESRAD modeling discussed in Appendix C of the 100-N Area RDR/RAWP (DOE-RL 2006b), it is predicted that these constituents will not reach groundwater (and thus the Columbia River) within 1,000 years ^d .	Yes

^a "National Primary Drinking Water Regulations" (40 Code of Federal Regulations 141).

^b Radiation Protection of the Public and Environment (DOE Order 5400.5).

^c Based on the isotopic distribution of uranium in the 100 Area, the 30 µg/L MCL corresponds to 21.2 pCi/L. Concentration-to-activity calculations are documented in *Calculation of Total Uranium Activity Corresponding to a Maximum Contaminant Level for Total Uranium of 30 Micrograms per Liter in Groundwater* (BHI 2001).

^d Because the soil-partitioning coefficient values for benzo(a)anthracene, benzo(a)pyrene, benzo(b)fluoranthene, benzo(k)fluoranthene, and indeno(1,2,3-cd)pyrene are greater than 80 mL/g (360 mL/g, 5,500 mL/g, 880 mL/g, 2,020 mL/g, and 3,470 mL/g, respectively), RESRAD modeling discussed in Appendix C of the 100-N Area RDR/RAWP (DOE-RL 2006b) predicts the contaminants will not reach groundwater within 1,000 years. The vadose zone beneath the 100-N-25 excavation is approximately 17 m (55.8 ft) thick. Based on RESRAD modeling, constituents with a soil-partitioning coefficient of 4.4 mL/g or greater are not predicted to migrate through a vadose zone of this thickness and reach groundwater in 1,000 years. Therefore, residual concentrations of benzo(a)anthracene, benzo(a)pyrene, benzo(b)fluoranthene, benzo(k)fluoranthene, and indeno(1,2,3-cd)pyrene are predicted to be protective of groundwater and the Columbia River.

COPC = contaminant of potential concern

MCL = maximum contaminant level

NA = not applicable

RAG = remedial action goal

RDR/RAWP = Remedial Design Report/Remedial Action Work Plan

RESRAD = RESidual RADioactivity (dose model)

Soil cleanup levels were established in the 100-N Area ROD (EPA 1999) based in part on a limited ecological risk assessment. Although not required by the 100-N Area ROD, a comparison against ecological risk screening levels has been made for the 100-N-25 waste site contaminants of potential concern and other constituents (Appendix A). Ecological screening levels from *Washington Administrative Code* 173-340 were exceeded for boron and vanadium. The U.S. Environmental Protection Agency ecological soil screening levels were exceeded for antimony, manganese, vanadium, and zinc. Exceedance of screening values is intended to trigger additional evaluation and does not necessarily indicate the existence of risk to ecological receptors. Because concentrations of antimony, manganese, vanadium, and zinc are below Hanford Site or Washington State background values (note that state background values are only used when Hanford Site background values are not available), it is believed that the presence of these constituents does not pose a risk to ecological receptors. All exceedances will be evaluated in the context of additional lines of evidence for risk to ecological receptors as part of the final closeout decision for this site.

REMAINING SITES VERIFICATION PACKAGE FOR THE 100-N-25, FRENCH DRAIN 1 LIQUID WASTE SITE

STATEMENT OF PROTECTIVENESS

The 100-N-25, French Drain 1 Liquid Waste Site verification sampling data, site evaluations, and supporting documentation demonstrate that this site meets the objectives established in the *Remedial Design Report/Remedial Action Work Plan for the 100-N Area* (RDR/RAWP) (DOE-RL 2006b) and the *Interim Action Record of Decision for the 100-NR-1 and 100-NR-2 Operable Units, Hanford Site, Benton County, Washington* (100-N Area ROD) (EPA 1999). The results of verification sampling and modeling show that residual soil concentrations do not preclude any future uses (as bounded by the rural-residential scenario) and allow for unrestricted use of shallow zone soils (i.e., 4.6 m [15 ft] deep). The results also demonstrate that residual contaminant concentrations are protective of groundwater and the Columbia River. The 100-N-25 waste site was excavated to a depth of approximately 4 m (13 ft) below ground surface. Contamination above direct exposure levels was not observed in shallow zone soils and is concluded to not exist in deep zone soils; therefore, institutional controls to prevent uncontrolled drilling or excavation into the deep zone of the site are not required.

Soil cleanup levels were established in the 100-N Area ROD (EPA 1999) based in part on a limited ecological risk assessment. Although not required by the 100-N Area ROD, a comparison against ecological risk screening levels has been made for the 100-N-25 waste site contaminants of potential concern (COPCs) and other constituents (Appendix A). Ecological screening levels from *Washington Administrative Code* (WAC) 173-340 were exceeded for boron and vanadium. The U.S. Environmental Protection Agency (EPA) ecological soil screening levels were exceeded for antimony, manganese, vanadium, and zinc. Exceedance of screening values is intended to trigger additional evaluation and does not necessarily indicate the existence of risk to ecological receptors. Because concentrations of antimony, manganese, vanadium, and zinc are below Hanford Site or Washington State background values (note that state background values are only used when Hanford Site background values are not available), it is believed that the presence of these constituents does not pose a risk to ecological receptors. All exceedances will be evaluated in the context of additional lines of evidence for risk to ecological receptors as part of the final closeout decision for this site.

GENERAL SITE INFORMATION AND BACKGROUND

The 100-N-25, French Drain 1 Liquid Waste Site, part of the 100-NR-1 Operable Unit, is located approximately 82 m (270 ft) south of the location of the former 116-N-2, 1310-N Chemical Waste Storage Tank (Figure 1). The purpose of the french drain is unknown; however, the nearest structure was the 1105-N Administrative Office Trailer, which existed from 1975 to 1986. No above- or below-grade pipelines were found to have led to the drain; therefore, it was speculated that the drain was used for water runoff from the nearby office trailer roof or condensate from an air conditioning unit.

\\autocad01\cad_projects\rs_samplingfigures\100n\100-n-25_fig1.dwg

Legend

Demolished Building

Existing Building

SCALE 1:2000

20 0 20 40 80 meters

Overall Site Location Map
100-N-25

REMEDIAL ACTION SUMMARY

Prior to the start of the 100-N-25 waste site remediation, water hydrant 32 was moved from the west side of the waste site to the east side. The move was conducted on March 16, 2012.

Remedial action at the 100-N-25 waste site was performed between March 27 and 29, 2012. The excavation continued to an approximate depth of 4 m (13 ft) below ground surface resulting in approximately 333 bank cubic meters (436 bank cubic yards) of material removed for disposal at the Environmental Restoration Disposal Facility (ERDF). There was no evidence of a french drain. A small section of steel piping associated with the water hydrant that was moved was removed and disposed at the ERDF. No anomalous materials were encountered during the excavation. All material was direct loaded from the excavation into trucks for disposal at the ERDF. No overburden piles or waste staging pile areas are associated with the 100-N-25 waste site. The post-excavation civil survey is shown in Figure 2.

A site visit was performed on April 18, 2012, to observe the remediated 100-N-25 waste site. Figure 3 is a post-remediation photograph of the site.

VERIFICATION SAMPLING ACTIVITIES

Verification sampling was conducted at the 100-N-25 waste site on July 24, 2012. Sampling was conducted to support a determination that residual contaminant concentrations in the soil meet cleanup criteria specified in the 100-N Area RDR/RAWP (DOE-RL 2006b) and 100-N Area ROD (EPA 1999).

The verification sample results are provided in Appendix B and indicate that the waste removal action achieved compliance with the remedial action objectives (RAOs) and remedial action goals (RAGs) for the 100-N-25 waste site. The following subsections provide additional discussion of the information used to develop the verification sampling design. The statistical results of verification sampling are also summarized to support interim closure of the site. A more detailed discussion of the verification sampling can be found in the *Work Instruction for Verification Sampling of the 100-N-25, French Drain 1 Liquid Waste Site* (WCH 2012b).

Contaminants of Potential Concern

The COPCs for the 100-N-25 waste site were determined based upon available historical information. The Waste Information Data System and Stewardship Information System reports indicate the purpose of the drain is unknown. The nearest structure was the 1105-N Administrative Office Trailer, which existed from 1975 to 1986, and was located approximately 4.7 m (15.5 ft) south of the french drain. No above- or below-grade pipelines were found to have led to the drain; therefore, it is speculated that the drain was used for water runoff from the nearby office trailer roof or condensate from an air conditioning unit.


Figure 2. The 100-N-25 Post-Excavation Civil Survey.

Figure 3. Post-Remediation Photograph of the 100-N-25 Waste Site (April 18, 2012).



The COPC list included the expanded list of inductively coupled plasma (ICP) metals (antimony, arsenic, barium, beryllium, boron, cadmium, chromium [total] cobalt, copper, lead, manganese, molybdenum, nickel, selenium, silver, vanadium, and zinc) and mercury. In-process soil samples collected from the site following remediation detected total petroleum hydrocarbons (TPH) and polycyclic aromatic hydrocarbons (PAH); therefore, they were included as site COPCs. Nitrate was added as a COPC because of the nitrate contamination in the groundwater at the 100-N Area. To preclude holding time issues associated with ion chromatography (IC) anions EPA method 300.0 for nitrates, EPA method 353.2 was identified in the verification work instruction as the preferred analytical method for nitrates. However, the IC anions EPA method 300.0 analysis was inadvertently added to the chain of custody; therefore the reported results are included as part of the data set provided in Appendix B. Bromide, chloride, fluoride, nitrite, phosphate, and sulfate are not considered COPCs for this site.

The analytical methods that were performed to evaluate the site COPCs are provided in Table 1.

Table 1. Laboratory Analytical Methods.

Analytical Method	Contaminant of Potential Concern
ICP metals ^a – EPA Method 6010	Metals
Mercury – EPA Method 7471	Mercury
IC anions – EPA Method 300.0 ^b	Nitrate
NO ₂ /NO ₃ – EPA Method 353.2	Nitrate
PAH – EPA Method 8310	Polycyclic aromatic hydrocarbons
TPH – EPA Method NWTPH-Dx	Total petroleum hydrocarbons

^a Analysis was performed for the expanded list of ICP metals to include antimony, arsenic, barium, beryllium, boron, cadmium, chromium (total), cobalt, copper, lead, manganese, molybdenum, nickel, selenium, silver, vanadium, and zinc.

^b The IC anions analysis by EPA method 300.0 was not required by the work instruction (WCH 2012b) and was inadvertently added to the chain of custody during sampling.

EPA = U.S. Environmental Protection Agency

IC = ion chromatography

ICP = inductively coupled plasma

NWTPH-Dx = Northwest total petroleum hydrocarbons-diesel range organics

PAH = polycyclic aromatic hydrocarbons

TPH = total petroleum hydrocarbons

Verification Sample Design

The 100-N-25 waste site consisted of a single decision unit, the excavation footprint, for verification sampling. Twelve statistical verification soil samples and a duplicate were collected from the excavation footprint. All sampling was performed in accordance with ENV-1, *Environmental Monitoring & Management*, to fulfill the requirements of the *100-N Area Sampling and Analysis Plan for CERCLA Waste Sites* (DOE-RL 2006a). All samples were grab samples collected at the predetermined coordinates. Additional information related to verification sampling can be found in the field sampling logbook (WCH 2012a). The verification sample summary is provided in Table 2. Figure 4 shows the waste site footprint and the sampling locations.

Verification Sample Results

All verification samples were analyzed using EPA-approved analytical methods. Evaluation of the verification data from the 100-N-25 excavation was performed by direct comparison of the statistical or maximum sample results for each COPC against the cleanup criteria.

The primary statistical calculation to evaluate compliance with cleanup standards is the 95% upper confidence limit (UCL) on the arithmetic mean of the data. The 95% UCL values for each detected COPC are computed for the 100-N-25 excavation decision unit as specified by the 100-N Area RDR/RAWP (DOE-RL 2006b). The calculations are provided in Appendix B. When a nonradionuclide COPC was detected in fewer than 50% of the verification samples collected for a decision unit, the maximum detected value was used for comparison to RAGs. If no detections for a given COPC were reported in the data set, then no statistical calculation or evaluation was performed for that COPC.

Table 2. 100-N-25 Waste Site Verification Sample Summary Table.

Sample Location	HEIS Sample Number	WSP Northing (m)	WSP Easting (m)	Sample Analysis ^a
EXC-1	J1PVN7	149520.4	571425.9	ICP metals ^b , mercury, NO ₂ /NO ₃ , IC anions ^c , PAH, TPH
EXC-2	J1PVN8	149520.4	571430.0	ICP metals ^b , mercury, NO ₂ /NO ₃ , IC anions ^c , PAH, TPH
EXC-3	J1PVN9	149523.9	571423.9	ICP metals ^b , mercury, NO ₂ /NO ₃ , IC anions ^c , PAH, TPH
EXC-4	J1PVP0	149523.9	571427.9	ICP metals ^b , mercury, NO ₂ /NO ₃ , IC anions ^c , PAH, TPH
EXC-5	J1PVP1	149523.9	571432.0	ICP metals ^b , mercury, NO ₂ /NO ₃ , IC anions ^c , PAH, TPH
EXC-6	J1PVP2	149527.4	571421.9	ICP metals ^b , mercury, NO ₂ /NO ₃ , IC anions ^c , PAH, TPH
EXC-7	J1PVP3	149527.4	571425.9	ICP metals ^b , mercury, NO ₂ /NO ₃ , IC anions ^c , PAH, TPH
EXC-8	J1PVP4	149527.4	571430.0	ICP metals ^b , mercury, NO ₂ /NO ₃ , IC anions ^c , PAH, TPH
EXC-9	J1PVP5	149527.4	571434.0	ICP metals ^b , mercury, NO ₂ /NO ₃ , IC anions ^c , PAH, TPH
EXC-10	J1PVP6	149530.9	571423.9	ICP metals ^b , mercury, NO ₂ /NO ₃ , IC anions ^c , PAH, TPH
EXC-11	J1PVP7	149530.9	571427.9	ICP metals ^b , mercury, NO ₂ /NO ₃ , IC anions ^c , PAH, TPH
EXC-12	J1PVP8	149530.9	571432.0	ICP metals ^b , mercury, NO ₂ /NO ₃ , IC anions ^c , PAH, TPH
Duplicate of EX-4	J1PVP9	149523.9	571427.9	ICP metals ^b , mercury, NO ₂ /NO ₃ , IC anions ^c , PAH, TPH
Equipment blank	J1PVR0	NA	NA	ICP metals ^b , mercury

^a Full protocol laboratory sample analysis was performed as defined in Table 1.

^b Analysis for the expanded list of ICP metals included antimony, arsenic, barium, beryllium, boron, cadmium, chromium (total), cobalt, copper, lead, manganese, molybdenum, nickel, selenium, silver, vanadium, and zinc.

^c The IC anions analysis by EPA method 300.0 was inadvertently added to the chain of custody. Bromide, chloride, fluoride, nitrite, phosphate, and sulfate are not considered contaminants of potential concern for this site.

EPA = U.S. Environmental Protection Agency

HEIS = Hanford Environmental Information System

ICP = inductively coupled plasma


IC = ion chromatography

NA = not applicable

PAH = polycyclic aromatic hydrocarbons

TPH = total petroleum hydrocarbons – diesel range organics

WSP = Washington State Plane

Figure 4. Verification Sample Locations for the 100-N-25 Waste Site Excavation.

Comparisons of the results for each COPC from the 100-N-25 excavation against the RAGs are summarized in Table 3. Contaminants that were not detected by laboratory analysis are excluded from the table. Calculated cleanup levels are not presented in the Cleanup Levels and Risk Calculations Database (Ecology 2012) under WAC 173-340-740(3) for calcium, magnesium, potassium, silicon, and sodium. The EPA's *Risk Assessment Guidance for Superfund* (EPA 1989) recommends that aluminum and iron not be considered in site risk evaluations. Therefore, aluminum, calcium, iron, magnesium, potassium, silicon, and sodium are not considered site COPCs and are also not included the table. The complete laboratory results for all constituents are stored in the Environmental Restoration (ENRE) project-specific database prior to archival in Hanford Environmental Information System (HEIS), and are presented in Attachment 1 of the 95% UCL calculations (Appendix B).

Table 3. Comparison of Statistical Sample Contaminant Concentrations to Remedial Action Goals for the 100-N-25 Waste Site Verification Sampling Data. (2 Pages)

COPC	Statistical or Maximum Result ^b (mg/kg)	Remedial Action Goals (mg/kg) ^a			Does the Result Exceed RAGs?	Does the Result Pass RESRAD Modeling?
		Direct Exposure	Soil Cleanup Level for Groundwater Protection	Soil Cleanup Level for River Protection		
Antimony ^c	1.0 (<BG)	32	5 ^d	5 ^d	No	--
Arsenic	2.0 (<BG)	20 ^d	20 ^d	20 ^d	No	--
Barium	62.0 (<BG)	16,000	200	400	No	--
Beryllium	0.19 (<BG)	10.4 ^e	1.51 ^d	1.51 ^d	No	--
Boron ^f	1.4	16,000	320	-- ^g	No	--
Cadmium ^c	0.14 (<BG)	13.9 ^e	0.81 ^d	0.81 ^d	No	--
Chromium	9.8 (<BG)	120,000	18.5 ^d	18.5 ^d	No	--
Cobalt	9.3 (<BG)	1,600	32	-- ^g	No	--
Copper	16.5 (<BG)	2,960	59.2	22.0 ^d	No	--
Lead	5.6 (<BG)	353	10.2 ^d	10.2 ^d	No	--
Manganese	329 (<BG)	11,200	512 ^d	NA	No	--
Molybdenum ^f	0.36	400	8	-- ^g	No	--
Nickel	11.6 (<BG)	1,600	19.1 ^d	27.4	No	--
Vanadium	62.7 (<BG)	560	85.1 ^d	-- ^g	No	--
Zinc	50.8 (<BG)	24,000	480	67.8 ^d	No	--
Chloride	23.4 (<BG)	--	25,000	-- ^g	No	--
Fluoride	0.83 (<BG)	4,800	96	400	No	--
Nitrogen in nitrate	23.7	128,000	1,000	2,000	No	--
Nitrogen in nitrite and nitrate	103	128,000	1,000	2,000	No	--
Sulfate	28.8 (<BG)	--	25,000	-- ^g	No	--
TPH – diesel range	7.157	NA	200	200	No	--
TPH – diesel range (extended)	14.657	NA	200	200	No	--
Acenaphthene	0.022	4,800	96	129	No	--
Anthracene	0.027	24,000	240	1,920	No	--
Benzo(a)anthracene	0.047	1.37	0.015 ^h	0.015 ^h	Yes	Yes ⁱ

Table 3. Comparison of Statistical Sample Contaminant Concentrations to Remedial Action Goals for the 100-N-25 Waste Site Verification Sampling Data. (2 Pages)

COPC	Statistical or Maximum Result ^b (mg/kg)	Remedial Action Goals (mg/kg) ^a			Does the Result Exceed RAGs?	Does the Result Pass RESRAD Modeling?
		Direct Exposure	Soil Cleanup Level for Groundwater Protection	Soil Cleanup Level for River Protection		
Benzo(a)pyrene	0.040	0.137	0.015 ^h	0.015 ^h	Yes	Yes ⁱ
Benzo(b)fluoranthene	0.049	1.37	0.015 ^h	0.015 ^h	Yes	Yes ⁱ
Benzo(ghi)perylene ^j	0.057	2,400	48	192	No	--
Benzo(k)fluoranthene	0.018	13.7	0.12	0.015 ^h	Yes	Yes ⁱ
Chrysene	0.056	137	1.2	0.10 ^h	No	--
Dibenz(a,h)anthracene	0.029	0.137	0.03 ^h	0.03 ^h	No	--
Fluoranthene	0.086	3,200	64	18.0	No	--
Fluorene	0.018	3,200	64	260	No	--
Indeno(1,2,3-cd)pyrene	0.067	1.37	0.015 ^h	0.015 ^h	Yes	Yes ⁱ
Phenanthrene ^j	0.094	24,000	240	1,920	No	--
Pyrene	0.093	2,400	48	192	No	--

^a Remedial action goals obtained from the 100-N Area RDR/RAWP (DOE-RL 2006b).

^b Maximum or 95% UCL, depending on data censorship, as described in the *100-N-25 Waste Site Cleanup Verification 95% UCL Calculation* (Appendix B).

^c Hanford Site-specific background not available. Value is Washington State background from *Natural Background Soil Metals Concentrations in Washington State* (Ecology 1994).

^d Where cleanup levels are less than background, cleanup levels default to background per WAC 173-340-700(4)(d), (Ecology 1996). The arsenic cleanup level of 20 mg/kg has been agreed to by the Tri-Party Agreement project managers as discussed in Section 2.12.1 of the 100-N Area RDR/RAWP (DOE-RL 2006b).

^e Carcinogenic cleanup level calculated based on the inhalation exposure pathway (WAC 173-340-750[3], Ecology 1996) using an airborne particulate mass-loading rate of 0.0001 g/m³ (*Hanford Guidance for Radiological Cleanup* [WDOH 1997]).

^f No Hanford Site-specific or Washington State background value available.

^g No parameters (bioconcentration factors or AWQC values) are available from the Ecology Cleanup Levels and Risk Calculations database or other databases to calculate cleanup levels (WAC 173-340-730[3][a][iii], 1996 [Method B for surface waters]).

^h Where cleanup levels are less than the RDLs, cleanup levels default to RDLs per WAC 173-340-707(2) (Ecology 1996). The cited RDLs are based on EPA-approved analytical methods that may not be available for rapid turnaround analyses.

ⁱ Because the soil-partitioning coefficient values for benzo(a)anthracene, benzo(a)pyrene, benzo(b)fluoranthene, benzo(k)fluoranthene, and indeno(1,2,3-cd)pyrene are greater than 80 mL/g (360 mL/g, 5,500 mL/g, 880 mL/g, 2,020 mL/g, and 3,470 mL/g, respectively), RESRAD modeling discussed in Appendix C of the 100-N Area RDR/RAWP (DOE-RL 2006b) predicts the contaminants will not reach groundwater within 1,000 years. The vadose zone beneath the 100-N-25 excavation is approximately 17 m (55.8 ft) thick. Based on RESRAD modeling, constituents with a soil-partitioning coefficient of 4.4 mL/g or greater are not predicted to migrate through a vadose zone of this thickness and reach groundwater in 1,000 years. Therefore, residual concentrations of benzo(a)anthracene, benzo(a)pyrene, benzo(b)fluoranthene, benzo(k)fluoranthene, and indeno(1,2,3-cd)pyrene are predicted to be protective of groundwater and the Columbia River.

^j Toxicity data for this chemical are not available. Cleanup levels are based on surrogate chemicals:

Contaminant: benzo(ghi)perylene; surrogate: pyrene

Contaminant: phenanthrene; surrogate: anthracene

-- = not applicable

AWQC = ambient water quality criteria

BG = background

COPC = contaminant of potential concern

Ecology = Washington State Department of Ecology

EPA = U.S. Environmental Protection Agency

NA = not available

RAG = remedial action goal

RDL = required detection limit

RDR/RAWP = Remedial Design Report/Remedial Action Work Plan

RESRAD = RESidual RADioactivity (dose model)

TPH = total petroleum hydrocarbons

UCL = upper confidence limit

WAC = Washington Administrative Code

DATA EVALUATION

This section demonstrates that contaminant concentrations at the 100-N-25 waste site achieve the applicable RAGs developed to support unrestricted land use at the 100 Area as established in the 100-N Area ROD (EPA 1999) and documented in the RDR/RAWP (DOE-RL 2006b).

Attainment of Nonradionuclide RAGs

Table 3 compares the verification sample values to the applicable soil RAGs for direct exposure, protection of groundwater, and protection of the Columbia River. Evaluation of the results indicates that residual concentrations of all COPCs are below the direct exposure soil RAGs for the 100-N-25 excavation. All COPCs were quantified below groundwater and/or river protection soil RAGs with the exception of benzo(a)anthracene, benzo(a)pyrene, benzo(b)fluoranthene, benzo(k)fluoranthene, and indeno(1,2,3-cd)pyrene. Because the soil-partitioning coefficient values for benzo(a)anthracene, benzo(a)pyrene, benzo(b)fluoranthene, benzo(k)fluoranthene and indeno(1,2,3-cd)pyrene are greater than 80 mL/g (360 mL/g, 5,500 mL/g, 880 mL/g, 2,020 mL/g, and 3,470 mL/g, respectively), RESidual RADioactivity (RESRAD) modeling discussed in Appendix C of the 100-N Area RDR/RAWP (DOE-RL 2006b) predicts the contaminants will not reach groundwater within 1,000 years. The vadose zone beneath the 100-N-25 excavation is approximately 17 m (55.8 ft) thick. Based on RESRAD modeling, constituents with a soil-partitioning coefficient of 4.4 mL/g or greater are not predicted to migrate through a vadose zone of this thickness and reach groundwater in 1,000 years. Therefore, residual concentrations of benzo(a)anthracene, benzo(a)pyrene, benzo(b)fluoranthene, benzo(k)fluoranthene, and indeno(1,2,3-cd)pyrene are predicted to be protective of groundwater (and thus the Columbia River).

Three-Part Test for Nonradionuclides

A RAG requirement for nonradionuclides is the WAC 173-340-740(7)(e) three-part test, which consists of the following criteria: (1) the cleanup verification 95% UCL value must be less than the cleanup level, (2) no single detection shall exceed two times the cleanup criteria, and (3) the percentage of samples exceeding the cleanup criteria must be less than 10% of the data set.

The application of the three-part test for the 100-N-25 waste site excavation is included in the statistical calculations, where half or more of the data set was detected (Appendix B). The results of this evaluation indicate that residual COPC concentrations pass the three-part test in comparison against applicable RAGs, with the exception of benzo(a)anthracene, benzo(a)pyrene, benzo(b)fluoranthene, benzo(k)fluoranthene, and chrysene, which fail one or more parts of the three-part test. However, because the soil-partitioning coefficient values for benzo(a)anthracene, benzo(a)pyrene, benzo(b)fluoranthene, benzo(k)fluoranthene, and chrysene are greater than 80 mL/g (360 mL/g, 5,500 mL/g, 880 mL/g, 2,020 mL/g, and 200 mL/g respectively), RESRAD modeling discussed in Appendix C of the 100-N Area RDR/RAWP (DOE-RL 2006b) predicts the contaminants will not reach groundwater within 1,000 years. The vadose zone beneath the 100-N-25 excavation is approximately 17 m (55.8 ft) thick. Based on RESRAD modeling, constituents with a soil-partitioning coefficient of 4.4 mL/g or greater are not predicted to migrate through a vadose zone of this thickness and reach groundwater in 1,000 years.

Therefore, residual concentrations of benzo(a)anthracene, benzo(a)pyrene, benzo(b)fluoranthene, benzo(k)fluoranthene, and chrysene are predicted to be protective of groundwater (and thus the Columbia River).

An additional application of the three-part test is included for the statistical data sets that default to the maximum because less than half of the data set was detected. The results of this evaluation indicate that residual COPC concentrations pass the three-part test in comparison against applicable RAGs with the exception of indeno(1,2,3-cd)pyrene which fail all three parts of the three-part test. However, because the soil-partitioning coefficient value for indeno(1,2,3-cd)pyrene (3,470 mL/g) is greater than 80 mL/g, RESRAD modeling discussed in Appendix C of the RDR/RAWP (DOE-RL 2006b) predicts the contaminant will not reach groundwater within 1,000 years. As stated above, the vadose zone beneath the 100-N-25 excavation is approximately 17 m (55.8 ft) thick. Based on RESRAD modeling, constituents with a soil-partitioning coefficient of 4.4 mL/g or greater are not predicted to migrate through a vadose zone of this thickness and reach groundwater in 1,000 years. Therefore, residual concentrations of indeno(1,2,3-cd)pyrene is predicted to be protective of groundwater (and thus the Columbia River).

Nonradionuclide Direct Contact Hazard Quotient and Carcinogenic Risk RAGs Attained

Nonradionuclide risk requirements include an individual hazard quotient of less than 1.0, a cumulative hazard quotient of less than 1.0, an individual contaminant carcinogenic risk of less than 1×10^{-6} , and a cumulative carcinogenic risk of less than 1×10^{-5} . For the 100-N-25 waste site, these risk values were not calculated for constituents that were either not detected or were detected at concentrations below Hanford Site or Washington State background. All individual hazard quotients for noncarcinogenic constituents were less than 1.0. The cumulative hazard quotient for those noncarcinogenic constituents above background or detected levels is 1.9×10^{-3} . The individual carcinogenic risk values for the carcinogenic constituents detected above background are less than 1×10^{-6} , and the cumulative carcinogenic risk value was 6.2×10^{-7} , which is less than 1×10^{-5} . The 100-N-25 waste site meets the requirements for the direct contact hazard quotient and excess carcinogenic risk as identified in the 100-N Area RDR/RAWP (DOE-RL 2006b).

Nonradionuclide Groundwater Hazard Quotient and Carcinogenic Risk RAGs Attained

Assessment of the risk requirements for the 100-N-25 waste site included calculation of the hazard quotient and carcinogenic (excess cancer) risk values for groundwater protection for nonradionuclides. The requirements include an individual and cumulative hazard quotient of less than 1.0, an individual excess carcinogenic risk of less than 1×10^{-6} , and a cumulative excess carcinogenic risk of less than 1×10^{-5} . Risk values were calculated for constituents that were detected at concentrations above Hanford Site or Washington State background values or for which there is no background value. In addition, the distribution coefficients for these contaminants must be less than that necessary to show no migration to groundwater in 1,000 years based on RESRAD modeling discussed in Appendix C of the 100-N Area RDR/RAWP (DOE-RL 2006b). Based on this model and a vadose zone of approximately 17 m (55.8 ft) in thickness, a distribution coefficient (K_d) of 4.4 or greater is required to show no

predicted migration to groundwater in 1,000 years. All individual hazard quotients for noncarcinogenic constituents are less than 1.0. The cumulative hazard quotient for the 100-N-25 waste site is 1.1×10^{-1} , which is less than 1.0. No carcinogenic constituents from groundwater met the criteria for evaluation at the 100-N-25 waste site; therefore, no calculations of excess carcinogenic risk were performed. Therefore, nonradionuclide risk requirements related to groundwater are met.

DATA QUALITY ASSESSMENT

A data quality assessment (DQA) was performed to compare the verification sampling approach (WCH 2012b), the field logbook (WCH 2012a), and resulting analytical data with the sampling and data quality requirements specified by the project objectives and performance specifications.

The DQA for the 100-N-25 waste site established that the data are of the right type, quality, and quantity to support site closeout decisions within specified error tolerances. The evaluation verified that the sample design was sufficient for the purpose of clean site verification. The cleanup verification sample analytical data are stored in the ENRE project-specific database for data evaluation prior to archival in the HEIS and are summarized in Appendix C.

SUMMARY FOR INTERIM CLOSURE

The 100-N-25 waste site has been evaluated in accordance with the 100-N Area ROD (EPA 1999) and the 100 Area RDR/RAWP (DOE-RL 2006). Verification sampling was performed, and the analytical results indicate that the residual concentrations of COPCs at the site meet the RAOs for direct exposure, groundwater protection, and river protection.

In accordance with this evaluation, the verification sampling results support a reclassification of the 100-N-25 waste site to interim closed out. Institutional controls to prevent uncontrolled drilling or excavation into the deep zone of the site are not required.

REFERENCES

40 CFR 141, "National Primary Drinking Water Regulations," *Code of Federal Regulations*, as amended.

BHI, 2001, *Calculation of Total Uranium Activity Corresponding to a Maximum Contaminant Level for Total Uranium of 30 Micrograms per Liter in Groundwater*, 0100X-CA-V0038, Rev. 0, Bechtel Hanford, Inc., Richland, Washington.

DOE Order 5400.5, *Radiation Protection of the Public and the Environment*, as amended, U.S. Department of Energy, Washington, D.C.

- DOE-RL, 2006a, *100-N Area Sampling and Analysis Plan for CERCLA Waste Sites*, DOE/RL-2005-92, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington.
- DOE-RL, 2006b, *Remedial Design Report/Remedial Action Work Plan for the 100-N Area*, DOE/RL-2005-93, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington.
- DOE-RL, 2011, *Tri-Party Agreement Handbook Management Procedures*, RL-TPA-90-0001, Guideline Number TPA-MP-14, "Maintenance of the Waste Information Data System (WIDS)," Rev. 2, U.S. Department of Energy, Richland Operations Office, Richland, Washington.
- Ecology, 1994, *Natural Background Soil Metals Concentrations in Washington State*, Publication No. 94-115, Washington State Department of Ecology, Olympia, Washington.
- Ecology, 1996, "Model Toxics Control Act – Cleanup," *Washington Administrative Code* (WAC) 173-340, Washington State Department of Ecology, Olympia, Washington.
- Ecology, 2012, *Cleanup Levels and Risk Calculations (CLARC) Database*, Washington State Department of Ecology, Olympia, Washington,
<<https://fortress.wa.gov/ecy/clarc/CLARCHome.aspx>>.
- ENV-1, *Environmental Monitoring & Management*, Washington Closure Hanford, Richland, Washington.
- EPA, 1989, *Risk Assessment Guidance for Superfund: Volume 1, Human Health Evaluation Manual, Part A; Interim Final*, EPA/540/1-89/002, U.S. Environmental Protection Agency, Washington, D.C.
- EPA, 1999, *Interim Action Record of Decision for the 100-NR-1 and 100-NR-2 Operable Units, Hanford Site, Benton County, Washington*, U.S. Environmental Protection Agency, Region 10, Seattle, Washington.
- WAC 173-340, 1996, "Model Toxics Control Act – Cleanup," *Washington Administrative Code*.
- WCH 2012a, *100-N Field Remediation and Sampling*, Logbook EL-1652-06, pp. 67-69, Washington Closure Hanford, Richland, Washington.
- WCH, 2012b, *Work Instruction for Verification Sampling of the 100-N-25, French Drain 1 Liquid Waste Site*, 0100N-WI-G0046, Rev. 0, Washington Closure Hanford, Richland, Washington.
- WDOH, 1997, *Hanford Guidance for Radiological Cleanup*, WDOH/320-015, Rev. 1, Washington State Department of Health, Olympia, Washington.

APPENDIX A
ECOLOGICAL RISK COMPARISON TABLE

Table A-1. Maximum Contaminant Concentrations that Exceed Ecological Screening Levels for the 100-N-25 Waste Site^a.

Hazardous Substance	2001 WAC 173-340 Table 749-3		EPA Ecological Soil Screening Levels ^b				Maximum Result
	Plants	Soil Biota	Wildlife	Plants	Soil Biota	Avian ^c	Mammalian ^c
	Metals (mg/kg)						
Antimony	5	NA	NA	NA	78	NA	0.27
Boron	NA	NA	NA	NA	NA	NA	1.4
Manganese	512	1,100 ^d	1,500	220	450	4,300	329 (<BG)
Vanadium	85.1	2	NA	NA	NA	7.8	62.7 (<BG)
Zinc	67.8	86 ^d	360	160	120	46	50.8 (<BG)

NOTE: Shaded cells indicate screening values that are exceeded.

^a Exceedance of screening values does not necessarily indicate the existence of risk to ecological receptors. All exceedances must be evaluated in the context of additional lines of evidence for ecological effects following a baseline risk assessment for the river corridor portion of the Hanford Site, which will include a more complete quantitative ecological risk assessment.

^b Available on the Internet at www.epa.gov/ecotox/ecossl.

^c Wildlife.

^d Benchmark replaced by Washington state natural background concentration from Ecology, 1994, *Natural Background Soil Metals Concentrations in Washington State*, Publication 94-115, Washington State Department of Ecology, Olympia, Washington.

BG = background

EPA = U.S. Environmental Protection Agency

NA = not available

WAC = Washington Administrative Code

APPENDIX B
CALCULATIONS

APPENDIX B**CALCULATION BRIEF**

The calculations provided in this appendix are copies of originals that are kept in the active Washington Closure Hanford project files and are available upon request. When the project is completed, the file will be stored in a U.S. Department of Energy, Richland Operations Office, repository. These calculations have been prepared in accordance with ENG-1, *Engineering Services*, ENG-1-4.5, "Project Calculation," Washington Closure Hanford, Richland, Washington. The calculations provided in this appendix include:

100-N-25 Waste Site Cleanup Verification 95% UCL Calculation, 0100N-CA-V0151, Rev. 0, Washington Closure Hanford, Richland, Washington.

100-N-25 Waste Site Direct Contact Hazard Quotient and Carcinogenic Risk Calculations, 0100N-CA-V0152, Rev. 0, Washington Closure Hanford, Richland, Washington.

100-N-25 Waste Site Hazard Quotient and Carcinogenic Risk Calculation for Protection of Groundwater, 0100N-CA-V0153, Rev. 0, Washington Closure Hanford, Richland, Washington.

DISCLAIMER FOR CALCULATIONS

The calculations that are provided in this appendix have been generated to document compliance with established cleanup levels. These calculations should be used in conjunction with other relevant documents in the administrative record.

CALCULATION COVER SHEETProject Title: 100-N Field Remediation Job No. 14655Area: 100-NDiscipline: Environmental *Calculation No: 0100N-CA-V0151Subject: 100-N-25 Waste Site Cleanup Verification 95% UCL CalculationComputer Program: Excel Program No: Excel 2003

The attached calculations have been generated to document compliance with established cleanup levels. These calculations should be used in conjunction with other relevant documents in the administrative record.

Committed Calculation ☒Preliminary ☐Superseded ☐Voided ☐

Rev.	Sheet Numbers	Originator	Checker	Reviewer	Approval	Date
0	Cover = 1 Sheets = 13 Attn. 1 = 4 Total = 18	J. D. Skoglie <i>J. D. Skoglie</i>	C. H. Dobie <i>C. H. Dobie</i>	N. K. Schiffern <i>N. K. Schiffern</i>	D. F. Obenauer <i>D. F. Obenauer</i>	12/20/12

SUMMARY OF REVISION

Washington Closure Hanford

CALCULATION SHEET

Originator J. D. Skoglie
 Project 100-N Field Remediation
 Subject 100-N-25 Waste Sites Cleanup Verification 95% UCL Calculations

Date 10/15/12 Calc. No. 0100N-CA-V0151
 Job No. 14655 Checked C. H. Dobie

Rev. No. 0
 Date 10/15/12
 Sheet No. 1 of 13

1 **Summary**2 **Purpose:**

3 Calculate the 95% upper confidence limit (UCL) values to evaluate compliance with cleanup standards for the subject site. Also,
 4 perform the *Washington Administrative Code (WAC) 173-340-740(7)(e)* Model Toxics Control Act (MTCA) 3-part test for
 5 nonradionuclide analytes and calculate the relative percent difference (RPD) for primary-duplicate sample pairs for each
 6 contaminant of concern (COC) and contaminant of potential concern (COPC), as necessary.

8 **Table of Contents:**

9 Sheets 1 to 4 - Calculation Sheet Summary
 10 Sheet 5 to 8 - Calculation Sheet Verification Data (Statistical and Maximum) - Excavation
 11 Sheet 9 to 12 - Ecology Software (MTCASat) Results
 12 Sheet 13 - Calculation Sheet Duplicate Analysis
 13 Attachment 1 - 100-N-25, Verification Sampling Results (4 sheets)

16 **Given/References:**

- 17 1) Sample Results (Attachment 1).
- 18 2) DOE-RL, 2006a, *100-N Area Sampling and Analysis Plan for CERCLA Waste Sites*, DOE/RL-2005-92, Rev. 0, U.S.
 19 Department of Energy, Richland Operations Office, Richland, Washington.
- 20 3) DOE-RL, 2006b, *Remedial Design Report/Remedial Action Work Plan for the 100-N Area*, DOE/RL-2005-93, Rev. 0,
 21 U.S. Department of Energy, Richland Operations Office, Richland, Washington.
- 22 4) Ecology, 1992, *Statistical Guidance for Ecology Site Managers*, Publication #92-54, Washington Department of Ecology,
 23 Olympia, Washington.
- 24 5) Ecology, 1993, *Statistical Guidance for Ecology Site Managers*, Supplement S-6, Analyzing Site or Background Data with
 25 Below-detection Limit or Below-PQL Values (Censored Data Sets), Publication #92-54, Washington Department of Ecology,
 26 Olympia, Washington.
- 27 6) Ecology, 2011, *Cleanup Levels and Risk Calculations (CLARC) Database*, Washington State Department of Ecology, Olympia,
 28 Washington, <<https://fortress.wa.gov/ecy/clarc/CLARCHome.aspx>>.
- 29 7) EPA, 1989, *Risk Assessment Guidance for Superfund: Volume 1, Human Health Evaluation Manual, Part A; Interim Final*,
 30 EPA/540/1-89/002, U.S. Environmental Protection Agency, Washington, D. C.
- 31 8) WAC 173-340, 1996, "Model Toxic Control Act - Cleanup," Washington Administrative Code.

35 **Solution:**

36 Calculation methodology is described in Ecology Pub. #92-54 (Ecology 1992, 1993), below, and in the RDR/RAWP
 37 (DOE-RL 2006b). Use data from attached worksheets to perform the 95% UCL calculation for each analyte, the WAC
 38 173-340-740(7)(e) 3-part test for nonradionuclides, and the RPD calculations for each COC/COPC. The hazard quotient and
 39 carcinogenic risk calculations are located in a separate calculation brief as an appendix to the Remaining Sites Verification
 40 Package (RSVP).

42 **Calculation Description:**

43 The subject calculations were performed on statistical data from soil verification samples (Attachment 1) from the 100-N-25 waste
 44 site. The data were entered into an EXCEL 2003 spreadsheet and calculations performed by using the built-in spreadsheet
 45 functions and/or creating formulae within the cells. The statistical evaluation of data for use in accordance with the RDR/RAWP
 46 (DOE-RL 2006b) is documented by this calculation. Duplicate RPD results are used in evaluation of data quality within the RSVP
 47 for this site.



50 **Methodology:**

51 The 100-N-25 waste site underwent statistical sampling at one decision unit; excavation area.

52 Analytical results for all sampling locations are summarized in the tables provided on sheet 4. Further information of the sample
 53 data quality is presented in the data quality assessment section of the associated RSVP.

Washington Closure Hanford

CALCULATION SHEET

Originator J. D. Skoglie  Date 10/15/12 Calc. No. 0100N-CA-V0151 Rev. No. 0
 Project 100-N Field Remediation Job No. 14855 Checked C. H. Dobie  Date 10/15/12
 Subject 100-N-25 Waste Sites Cleanup Verification 95% UCL Calculations Sheet No. 2 of 13

1 Summary (continued)

2 Methodology, continued:

3 For nonradioactive analytes with ≤50% of the data below detection limits, the statistical value calculated to evaluate the
 4 effectiveness of cleanup is the 95% UCL. For nonradioactive analytes with >50% of the data below detection limits, as
 5 determined by direct inspection of the sample results (Attachment 1), the maximum detected value for the data set (which
 6 includes primary and duplicate samples) is used instead of the 95% UCL, and no further calculations are performed for those
 7 data sets. For convenience, these maximum detected values are included in the summary tables that follow. The 95% UCL
 8 was not calculated for data sets with no reported detections. Calculated cleanup levels are not available in (Ecology 2011) under
 9 WAC 173-340-740(3) for calcium, magnesium, potassium, silicon, and sodium. The EPA's *Risk Assessment Guidance for*
 10 *Superfund* (EPA 1989) recommends that aluminum and iron not be considered in site risk evaluations. Therefore, aluminum,
 11 calcium, iron, magnesium, potassium, silicon, and sodium are not considered site COCs/COPCs and are also not included in
 12 these calculations.

13 All nonradionuclide data reported as being undetected are set to ½ the detection limit value for calculation of the statistics
 14 (Ecology 1993). For the statistical evaluation of duplicate sample pairs, the samples are averaged before being included in the
 15 data set, after adjustments for censored data as described above. For radionuclide data, calculation of the statistics is done
 16 using the reported value. In cases where the laboratory does not report a value below the minimum detectable activity (MDA),
 17 half of the MDA is used in the calculation. For the statistical evaluation of duplicate sample pairs, the samples are averaged
 18 before being included in the data set, after adjustments for censored data as described above.

19 For nonradionuclides, the WAC 173-340 statistical guidance suggests that a test for distributional form be performed on the data
 20 and the 95% UCL calculated on the appropriate distribution using Ecology software. For nonradionuclide small data sets ($n <$
 21 10), the calculations are performed assuming nonparametric distribution, so no tests for distribution are performed. For
 22 nonradionuclide data sets of ten or greater, as for the subject site, distributional testing is done using Ecology's MTCASat
 23 software (Ecology 1993). Due to differences in addressing censored data between the RDR/RAWP
 24 (DOE-RL 2006b) and MTCASat coding and due to a limitation in the MTCASat coding (no direct capability to address variable
 25 quantitation limits within a data set), substitutions for censored data are performed before software input and the resulting data
 26 set treated as uncensored.

27 The WAC 173-340-740(7)(e) 3-part test is performed for nonradionuclide analytes only and determines if:

- 28 1) the 95% UCL exceeds the most stringent cleanup limit for each COPC/COC,
- 29 2) greater than 10% of the raw data exceed the most stringent cleanup limit for each COPC/COC,
- 30 3) the maximum value of the raw data set exceeds two times the most stringent cleanup limit for each COPC/COC.

31 The RPD is calculated when both the primary value and either the duplicate or split value for a given analyte are above
 32 detection limits and are greater than 5 times the target detection limit (TDL). The TDL is a laboratory detection limit pre-
 33 determined for each analytical method and is listed in Table 2-1 of the SAP (DOE-RL 2006a) for certain constituents. All other
 34 constituents will have their own pre-determined TDL's based on the laboratory and method used. Where direct evaluation of the
 35 attached sample data showed that a given analyte was not detected in the primary and/or duplicate sample, further evaluation of
 36 the RPD value was not performed. The RPD calculations use the following formula:

$$RPD = [|M-S| / ((M+S)/2)] * 100$$

where, M = Main Sample Value S = Split (or duplicate) Sample Value

37 For quality assurance/quality control (QA/QC) duplicate RPD calculations, a value less than 30% indicates the data compare
 38 favorably. If the RPD is greater than 30%, further investigation regarding the usability of the data is performed. To assist in the
 39 identification of anomalous sample pairs, when an analyte is detected in the primary or duplicate/split sample, but was quantified
 40 at less than 5 times the TDL in one or both samples, an additional parameter is evaluated. In this case, if the difference
 41 between the primary and duplicate/split result exceeds a control limit of 2 times the TDL, further assessment regarding the
 42 usability of the data is performed. Additional discussion as necessary is provided in the data quality assessment section of the
 43 applicable RSPV.

Washington Closure Hanford

CALCULATION SHEET

Originator J. D. Skoglie Date 09/12/12 Calc. No. 0100N-CA-V0151
 Project 100-N Field Remediation Job No. 14655 Checked C. H. Dobie
 Subject 100-N-25 Waste Sites Cleanup Verification 95% UCL Calculations

Rev. No. 0
 Date 09/12/12
 Sheet No. 3 of 13

1 Summary (continued)

2

3 QUALIFIER LIST

4

5 B = estimated result. Result is less than the RL, but greater than MDL.

6 C = analyte was detected in both the sample and the associated QC

7 blank, and the sample concentration was $\leq 5X$ the blank concentration.

8 J = estimate

9 M = sample duplicate precision not met

10 N = recovery exceeds upper or lower control limits.

11 U = undetected

12 X = more than 40% difference between columns, lower result reported (organics).

13 X = serial dilution in the analytical batch indicates that physical and chemical interferences are present (metals).

14

15 ACRONYM LIST

16

17 -- = not applicable

18 DE = direct exposure

19 GW = groundwater

20 MTCA = Model Toxics Control Act

21 PAH = polycyclic aromatic hydrocarbons

22 PQL = practical quantitation limit

23 Q = qualifier

24 QA/QC = quality assurance/quality control

25 RAG = remedial action goal

26 RDR/RAWP = remedial design report/remedial action work plan

27 RESRAD = RESidual RADioactivity (dose model)

28 RPD = relative percent difference

29 RSVP = remaining sites verification package

30 SAP = sampling and analysis plan

31 TDL = target detection limit

32 UCL = upper confidence limit

33 WAC = Washington Administrative Code

34

Washington Closure Hanford

CALCULATION SHEET

Originator J. D. Skoglie
 Project 100-N Field Remediation
 Subject 100-N-25 Waste Sites Cleanup Verification 95% UCL Calculations

Date 10/15/12
 Job No. 14655

Calc. No. 0100N-CA-V0151
 Checked C. H. Dobie

Rev. No. 0
 Date 10/15/12
 Sheet No. 4 of 13

1 Summary (continued)

2 Results:

3 The results presented in the tables that follow include the summary of the
 4 results of the 95% UCL calculations for the excavation, staging pile area, the
 5 WAC 173-340-740(7)(e) 3-part test evaluation, and the RPD calculations, and
 6 are for use in risk analysis and the RSVP for this site.

9 Results Summary - Excavation Area

Analyte	EXC		Units
	95% UCL Result	Maximum Result	
Antimony	1.0	--	mg/kg
Arsenic	2.0	--	mg/kg
Barium	62.0	--	mg/kg
Beryllium	0.19	--	mg/kg
Boron	1.4	--	mg/kg
Cadmium	0.14	--	mg/kg
Chromium	9.8	--	mg/kg
Cobalt	9.3	--	mg/kg
Copper	16.5	--	mg/kg
Lead	5.6	--	mg/kg
Manganese	329	--	mg/kg
Molybdenum	--	0.36	mg/kg
Nickel	11.6	--	mg/kg
Vanadium	62.7	--	mg/kg
Zinc	50.8	--	mg/kg
Chloride	23.4	--	mg/kg
Fluoride	0.83	--	mg/kg
Nitrogen in nitrate	23.7	--	mg/kg
Nitrogen in nitrate and nitrite	103	--	mg/kg
Sulfate	28.8	--	mg/kg
TPH - diesel range	7157	--	ug/kg
TPH - diesel range EXT	14657	--	ug/kg
Acenaphthene	--	22	ug/kg
Anthracene	--	27	ug/kg
Benzo(a)anthracene	47	--	ug/kg
Benzo(a)pyrene	40	--	ug/kg
Benzo(b)fluoranthene	49	--	ug/kg
Benzo(ghi)perylene	--	57	ug/kg
Benzo(k)fluoranthene	18	--	ug/kg
Chrysene	56	--	ug/kg
Dibenz(a,h)anthracene	--	29	ug/kg
Fluoranthene	86	--	ug/kg
Fluorene	--	18	ug/kg
Indeno(1,2,3-cd)pyrene	--	67	ug/kg
Phenanthrene	--	94	ug/kg
Pyrene	93	--	ug/kg

48 3-Part Test Evaluation:

	EXC	
95% UCL or maximum* > Cleanup Limit?	YES	YES
> 10% above Cleanup Limit?	YES	YES
Any sample > 2x Cleanup Limit?	YES	YES

53 *The 95% UCL result or maximum value, depending on data censorship, as
 54 described in the methodology section.

Relative Percent Difference Results and QA/QC Analysis*

Analyte	Duplicate Analysis
	EXC
Aluminum	1.7%
Barium	3.1%
Calcium	9.4%
Chromium	6.2%
Copper	3.7%
Iron	1.4%
Magnesium	5.0%
Manganese	2.5%
Silicon	4.0%
Sodium	19.7%
Vanadium	3.5%
Zinc	2.3%

*RPD listed where result produced, based on criteria. If RPD not required, no value is listed. The significance of the reported RPD values, including values greater than 30%, is addressed in the data quality assessment section of the RSVP.

CALCULATION SHEET

Washington Closure Hanford
Originator J. D. Skoglie
Project 100-N Field Remediation
Subject 100-N-25 Waste Sites Cleanup Verification 95% UCL Calculations

Date 10/15/12
Job No. 14655

Calc. No. 0100N-CA-V0151
Checked C. H. Dobie

Rev. No. 0
Date 10/15/12
Sheet No. 5 of 13

1 100-N-25 Statistical Calculations

2 Verification Data -Excavation (EXC)

Sample Area	Sample Number	Sample Date	Antimony			Arsenic			Barium			Beryllium			Boron			Cadmium			Chromium			Cobalt			Copper			Lead		
			mg/kg	Q	PQL	mg/kg	Q	PQL	mg/kg	Q	PQL	mg/kg	Q	PQL	mg/kg	Q	PQL	mg/kg	Q	PQL	mg/kg	Q	PQL	mg/kg	Q	PQL	mg/kg	Q	PQL	mg/kg	Q	PQL
EXC-4	J1PVP0	7/24/12	0.85	J	0.36	2.4		0.62	58.9	X	0.071	0.23		0.031	1.1	B	0.92	0.12	B	0.038	8.3	X	0.054	8.5	X	0.094	16.1		0.20	4.6		0.25
Duplicate of J1PVP0	J1PVP9	7/24/12	0.72	J	0.37	1.9		0.64	57.1	X	0.074	0.19		0.032	0.95	U	0.95	0.11	B	0.040	7.8	X	0.056	8.4	X	0.097	16.7		0.21	4.5		0.26
EXC-1	J1PVN7	7/24/12	1.6	JM	0.38	1.8		0.66	80.2	X	0.076	0.22		0.033	1.8	B	0.99	0.15	B	0.041	13.6	X	0.058	8.5	X	0.10	15.5		0.22	4.8		0.27
EXC-2	J1PVN8	7/24/12	1.0	J	0.36	1.8		0.62	57.1	X	0.071	0.21		0.031	1.5	B	0.92	0.14	B	0.038	9.3	X	0.054	8.7	X	0.094	16.3		0.20	4.0		0.25
EXC-3	J1PVN9	7/24/12	0.63	J	0.38	1.6		0.65	58.0	X	0.075	0.14	B	0.033	1.0	B	0.97	0.13	B	0.041	6.7	X	0.058	9.1	X	0.099	15.7		0.22	5.2		0.27
EXC-5	J1PVP1	7/24/12	0.99	J	0.34	2.3		0.59	44.1	X	0.068	0.16	B	0.029	0.87	U	0.87	0.12	B	0.037	7.3	X	0.052	8.4	X	0.089	14.1		0.19	4.1		0.24
EXC-6	J1PVP2	7/24/12	1.0	J	0.33	1.0		0.58	54.6	X	0.066	0.14	U	0.14	0.86	U	0.86	0.12	B	0.036	8.1	X	0.051	11.1	X	0.44	17.6		0.95	6.7		1.2
EXC-7	J1PVP3	7/24/12	0.64	J	0.32	1.9		0.56	61.2	X	0.065	0.19		0.028	1.1	B	0.83	0.14	B	0.035	10.0	X	0.049	8.7	X	0.085	15.9		0.18	6.7		0.23
EXC-8	J1PVP4	7/24/12	0.89	J	0.35	2.6		0.61	49.1	X	0.070	0.25		0.031	0.91	U	0.91	0.10	B	0.038	8.6	X	0.054	9.4	X	0.093	16.3		0.20	5.9		0.25
EXC-9	J1PVP5	7/24/12	0.66	J	0.37	1.7		0.65	54.7	X	0.075	0.14	B	0.033	1.6	B	0.97	0.14	B	0.040	7.7	X	0.057	8.9	X	0.099	14.1		0.21	4.3		0.27
EXC-10	J1PVP6	7/24/12	0.52	JB	0.37	1.8		0.65	63.8	X	0.074	0.16	B	0.032	1.0	B	0.96	0.12	B	0.040	9.6	X	0.057	7.9	X	0.098	15.3		0.21	6.0		0.26
EXC-11	J1PVP7	7/24/12	0.68	J	0.37	1.9		0.64	49.1	X	0.074	0.15	B	0.032	0.96	B	0.96	0.12	B	0.040	9.1	X	0.057	9.1	X	0.098	17.6		0.21	3.9		0.26
EXC-12	J1PVP8	7/24/12	0.73	J	0.35	0.99		0.61	54.8	X	0.070	0.13	B	0.031	0.91	U	0.91	0.14	B	0.038	7.7	X	0.054	8.9	X	0.093	15.4		0.20	4.3		0.25

19 Statistical Computation Input Data

Sample Area	Sample Number	Sample Date	Antimony mg/kg		Arsenic mg/kg		Barium mg/kg		Beryllium mg/kg		Boron mg/kg		Cadmium mg/kg		Chromium mg/kg		Cobalt mg/kg		Copper mg/kg		Lead mg/kg	
EXC-4	J1PVP0/J1PVP9	7/24/12	0.79		2.2		58.0		0.21		0.79		0.12		8.1		8.5		16.4		4.6	
EXC-1	J1PVN7	7/24/12	1.6		1.8		80.2		0.22		1.8		0.15		13.6		8.5		15.5		4.8	
EXC-2	J1PVN8	7/24/12	1.0		1.8		57.1		0.21		1.5		0.14		9.3		8.7		16.3		4.0	
EXC-3	J1PVN9	7/24/12	0.63		1.6		58.0		0.14		1.0		0.13		6.7		9.1		15.7		5.2	
EXC-5	J1PVP1	7/24/12	0.99		2.3		44.1		0.16		0.44		0.12		7.3		8.4		14.1		4.1	
EXC-6	J1PVP2	7/24/12	1.0		1.0		54.6		0.070		0.43		0.12		8.1		11.1		17.6		6.7	
EXC-7	J1PVP3	7/24/12	0.64		1.9		61.2		0.19		1.1		0.14		10.0		8.7		15.9		6.7	
EXC-8	J1PVP4	7/24/12	0.89		2.6		49.1		0.25		0.46		0.10		8.6		9.4		16.3		5.9	
EXC-9	J1PVP5	7/24/12	0.66		1.7		54.7		0.14		1.6		0.14		7.7		8.9		14.1		4.3	
EXC-10	J1PVP6	7/24/12	0.52		1.8		63.8		0.16		1.0		0.12		9.6		7.9		15.3		6.0	
EXC-11	J1PVP7	7/24/12	0.68		1.9		49.1		0.15		0.96		0.12		9.1		9.1		17.6		3.9	
EXC-12	J1PVP8	7/24/12	0.73		0.99		54.8		0.13		0.46		0.14		7.7		8.9		15.4		4.3	

34 Statistical Computations

		Antimony		Arsenic		Barium		Beryllium		Boron		Cadmium		Chromium		Cobalt		Copper		Lead	
95% UCL based on		Large data set (n ≥ 10), use MTCASat lognormal distribution.		Large data set (n ≥ 10), use MTCASat normal distribution.		Large data set (n ≥ 10), use MTCASat lognormal distribution.		Large data set (n ≥ 10), use MTCASat normal distribution.		Large data set (n ≥ 10), use MTCASat lognormal distribution.		Large data set (n ≥ 10), use MTCASat lognormal distribution.		Large data set (n ≥ 10), use MTCASat lognormal distribution.		Large data set (n ≥ 10), lognormal and normal distribution rejected, use z statistic.		Large data set (n ≥ 10), use MTCASat lognormal distribution.		Large data set (n ≥ 10), use MTCASat lognormal distribution.	
N		12		12		12		12		12		12		12		12		12		12	
% < Detection limit		0%		0%		0%		8%		33%		0%		0%		0%		0%		0%	
Mean		0.84		1.8		57.1		0.17		0.96		0.13		8.8		0.79		1.1		1.0	
Standard deviation		0.29		0.46		9.1		0.049		0.48		0.014		1.8		9.3		16.5		5.6	
95% UCL on mean		1.0		2.0		62.0		0.19		1.4		0.14		9.8		11.1		17.6		6.7	
Maximum value		1.6		2.6		80.2		0.25		1.8		0.15		13.6		11.1		17.6		6.7	
Most Stringent Cleanup Limit for nonradionuclide and RAG type (mg/kg)		5 GW & River Protection		20 DE, GW & River Protection		200 GW Protection		1.51 GW & River Protection		320 GW Protection		0.81 GW & River Protection		18.5 GW & River Protection		32 GW Protection		22.0 River Protection		10.2 GW & River Protection	
WAC 173-340 3-PART TEST																					
95% UCL > Cleanup Limit?		NA		NA		NA		NA		NO		NA		NA		NA		NA		NA	
> 10% above Cleanup Limit?		NA		NA		NA		NA		NO		NA		NA		NA		NA		NA	
Any sample > 2X Cleanup Limit?		NA		NA		NA		NA		NO		NA		NA		NA		NA		NA	
WAC 173-340 Compliance?		Because all values are below background (5 mg/kg) the WAC 173-340 3-part test is not required.		Because all values are below background (6.5 mg/kg) the WAC 173-340 3-part test is not required.		Because all values are below background (132 mg/kg) the WAC 173-340 3-part test is not required.		Because all values are below background (1.51 mg/kg) the WAC 173-340 3-part test is not required.		The data set meets the 3-part test criteria when compared to the most stringent RAG.		Because all values are below background (0.81 mg/kg) the WAC 173-340 3-part test is not required.		Because all values are below background (18.5 mg/kg) the WAC 173-340 3-part test is not required.		Because all values are below background (15.7 mg/kg) the WAC 173-340 3-part test is not required.		Because all values are below background (22.0 mg/kg) the WAC 173-340 3-part test is not required.		Because all values are below background (10.2 mg/kg) the WAC 173-340 3-part test is not required.	

Qualifiers are defined on sheet 3

CALCULATION SHEET

Washington Closure Hanford

Originator J. D. Skoglia

Project 100-N Field Remediation

Subject 100-N-25 Waste Sites Cleanup Verification 95% UCL Calculations

Date 10/15/12
Job No. 14655Calc. No. 0100N-CA-V0151
Checked C. H. DobieRev. No. 0
Date 10/15/12
Sheet No. 6 of 13

1 100-N-25 Statistical Calculations

2 Verification Data -Excavation (EXC)

Sample Area	Sample Number	Sample Date	Manganese			Nickel			Vanadium			Zinc			Chloride			Fluoride			Nitrogen in Nitrate			Nitrogen in Nitrite and Nitrate			Sulfate			TPH - Diesel Range		
			mg/kg	Q	PQL	mg/kg	Q	PQL	mg/kg	Q	PQL	mg/kg	Q	PQL	mg/kg	Q	PQL	mg/kg	Q	PQL	mg/kg	Q	PQL	mg/kg	Q	PQL	mg/kg	Q	PQL	ug/kg	Q	PQL
EXC-4	J1PVP0	7/24/12	322	X	0.094	10.3	X	0.12	53.5	X	0.088	44.3	X	0.37	3.2	B	1.9	0.99	B	0.81	2.5	J	0.31	2.3		0.29	7.5		1.7	2600	J	650
Duplicate of J1PVP0	J1PVP9	7/24/12	314	X	0.097	10.2	X	0.12	55.4	X	0.091	43.3	X	0.39	2.9	B	2.0	0.82	U	0.82	2.2	JB	0.31	2.0		0.29	7.3		1.7	2000	J	690
EXC-1	J1PVN7	7/24/12	347	X	0.10	10.9	X	0.12	54.6	X	0.095	53.7	X	0.40	3.5	B	2.0	0.85	U	0.85	1.5	JB	0.33	1.0	M	0.31	12.7		1.8	3900	J	700
EXC-2	J1PVN8	7/24/12	325	X	0.094	13.4	X	0.12	57.3	X	0.088	45.6	X	0.37	6.7		2.0	1.3	B	0.82	1.3	JB	0.31	0.88		0.30	15.8		1.7	870	J	640
EXC-3	J1PVN9	7/24/12	312	X	0.099	9.9	X	0.12	61.7	X	0.093	48.5	X	0.39	3.5	B	2.0	0.86	B	0.83	3.2	J	0.32	2.9		0.30	18.1		1.7	4300		670
EXC-5	J1PVP1	7/24/12	304	X	0.089	9.7	X	0.11	52.5	X	0.084	46.0	X	0.35	7.6		2.0	0.91	B	0.84	7.1	J	0.32	7.0		0.30	13.6		1.8	1100	J	680
EXC-6	J1PVP2	7/24/12	309	X	0.087	11.7	X	0.11	70.6	X	0.41	48.6	X	0.35	2.1	B	2.0	0.82	U	0.82	0.91	JB	0.31	0.29	U	0.29	3.7	B	1.7	5400		660
EXC-7	J1PVP3	7/24/12	327	X	0.085	11.3	X	0.10	59.7	X	0.080	47.3	X	0.34	5.4		1.9	1.0	B	0.81	8.1	J	0.31	8.2		0.29	15.1		1.7	3400	J	660
EXC-8	J1PVP4	7/24/12	358	X	0.093	13.3	X	0.11	60.3	X	0.087	48.5	X	0.37	6.4		2.0	0.85	U	0.85	15.0	J	0.32	16.5		0.31	30.8		1.8	1100	J	680
EXC-9	J1PVP5	7/24/12	316	X	0.099	10.3	X	0.12	62.8	X	0.093	61.1	X	0.39	83.9		2.0	0.84	U	0.84	2.9	J	0.32	2.9		0.30	8.3		1.8	3200	J	650
EXC-10	J1PVP6	7/24/12	311	X	0.098	10.1	X	0.12	57.2	X	0.092	46.9	X	0.39	10.3		1.9	0.94	B	0.81	10.2	J	0.31	11.0		0.30	19.6		1.7	6000		630
EXC-11	J1PVP7	7/24/12	317	X	0.098	10.8	X	0.12	66.1	X	0.092	46.2	X	0.39	16.3		2.0	0.83	U	0.83	26.8	J	0.32	27.4		0.30	35.9		1.7	2100	J	640
EXC-12	J1PVP8	7/24/12	304	X	0.093	9.0	X	0.11	61.4	X	0.087	47.0	X	0.37	2.0	B	1.9	0.81	U	0.81	0.59	JB	0.31	0.30	U	0.30	3.0	B	1.7	12000		620

19 Statistical Computation Input Data

Sample Area	Sample Number	Sample Date	Manganese			Nickel			Vanadium			Zinc			Chloride			Fluoride			Nitrogen in Nitrate			Nitrogen in Nitrite and Nitrate			Sulfate			TPH - Diesel Range		
			mg/kg			mg/kg			mg/kg			mg/kg			mg/kg			mg/kg			mg/kg			mg/kg			mg/kg			ug/kg		
EXC-4	J1PVP0/J1PVP9	7/24/12	318			10.3			54.5			43.8			3.1			0.70			2.4			2.2			7.4			2300		
EXC-1	J1PVN7	7/24/12	347			10.9			54.6			53.7			3.5			0.43			1.5			1.0			12.7			3900		
EXC-2	J1PVN8	7/24/12	325			13.4			57.3			45.6			6.7			1.3			1.3			0.88			15.8			870		
EXC-3	J1PVN9	7/24/12	312			9.9			61.7			48.5			3.5			0.86			3.2			2.9			18.1			4300		
EXC-5	J1PVP1	7/24/12	304			9.7			52.5			46.0			7.6			0.91			7.1			7.0			13.6			1100		
EXC-6	J1PVP2	7/24/12	309			11.7			70.6			48.6			2.1			0.41			0.91			0.15			3.7			5400		
EXC-7	J1PVP3	7/24/12	327			11.3			59.7			47.3			5.4			1.0			8.1			8.2			15.1			3400		
EXC-8	J1PVP4	7/24/12	358			13.3			60.3			48.5			6.4			0.43			15.0			16.5			30.8			1100		
EXC-9	J1PVP5	7/24/12	316			10.3			62.8			61.1			83.9			0.42			2.9			2.9			8.3			3200		
EXC-10	J1PVP6	7/24/12	311			10.1			57.2			46.9			10.3			0.94			10.2			11.0			19.6			6000		
EXC-11	J1PVP7	7/24/12	317			10.8			66.1			46.2			16.3			0.42			26.8			27.4			35.9			2100		
EXC-12	J1PVP8	7/24/12	304			9.0			61.4			47.0			2.0			0.41			0.59			0.15			3.0			12000		

34 Statistical Computations

	Manganese			Nickel			Vanadium			Zinc			Chloride			Fluoride			Nitrogen in Nitrate			Nitrogen in Nitrite and Nitrate			Sulfate			TPH - Diesel Range		
95% UCL based on	Large data set (n ≥ 10), lognormal and normal distribution rejected, use z-statistic.			Large data set (n ≥ 10), use MTCASat lognormal distribution.			Large data set (n ≥ 10), use MTCASat lognormal distribution.			Large data set (n ≥ 10), lognormal and normal distribution rejected, use z-statistic.			Large data set (n ≥ 10), lognormal and normal distribution rejected, use z-statistic.			Large data set (n ≥ 10), lognormal and normal distribution rejected, use z-statistic.			Large data set (n ≥ 10), use MT CASat lognormal distribution.			Large data set (n ≥ 10), use MTCASat lognormal distribution.			Large data set (n ≥ 10), use MTCASat lognormal distribution.			Large data set (n ≥ 10), use MTCASat lognormal distribution.		
N	12			12			12			12			12			12			12			12			12			12		
% < Detection limit	0%			0%			0%			0%			0%			50%			0%			17%			0%			0%		
Mean	321			10.9			59.9			48.6			12.6			0.68			6.7			6.7			15.3			3806		
Standard deviation	16.6			1.4			5.2			4.6			22.8			0.31			7.7			8.2			10.0			3071		
95% UCL on mean	329			11.6			62.7			50.8			23.4			0.83			23.7			103			28.8			7157		
Maximum value	358			13.4			70.6			61.1			83.9			1.3			26.8			27.4			35.9			12000		
Most Stringent Cleanup Limit for nonradionuclide and RAG type (mg/kg) unless stated otherwise	512	GW & River Protection		19.1	GW Protection		85.1	GW Protection		67.8	River Protection		25000	GW Protection		96	GW Protection		1000	GW Protection		1000	GW Protection		25000	GW Protection		200000	GW & River Protection	
WAC 173-340 3-PART TEST																														
95% UCL > Cleanup Limit?	NA			NA			NA			NA			NA			NA			NO			NO			NA			NO		
> 10% above Cleanup Limit?	NA			NA			NA			NA			NA			NA			NO			NO			NA			NO		
Any sample > 2X Cleanup Limit?	NA			NA			NA			NA			NA			NA			NO			NO			NA			NO		
WAC 173-340 Compliance?	Because all values are below background (512 mg/kg) the WAC 173-340 3-part test is not required.			Because all values are below background (19.1 mg/kg) the WAC 173-340 3-part test is not required.			Because all values are below background (85.1 mg/kg) the WAC 173-340 3-part test is not required.			Because all values are below background (67.8 mg/kg) the WAC 173-340 3-part test is not required.			Because all values are below background (100 mg/kg) the WAC 173-340 3-part test is not required.			Because all values are below background (2.81 mg/kg) the WAC 173-340 3-part test is not required.			The data set meets the 3-part test criteria when compared to the most stringent RAG.			The data set meets the 3-part test criteria when compared to the most stringent RAG.			Because all values are below background (237 mg/kg) the WAC 173-340 3-part test is not required.			The data set meets the 3-part test criteria when compared to the most stringent RAG.		

Qualifiers are defined on sheet 3

Washington Closure Hanford
Originator J. D. Skogile
Project 100-N Field Remediation
Subject 100-N-25 Waste Sites Cleanup Verification 95% UCL Calculations

Date 10/15/12
Job No. 14655

Calc. No. 0100N-CA-V0151
Checked C. H. Dobie

Rev. No. 0
Date 10/15/12
Sheet No. 7 of 13

CALCULATION SHEET

1 100-N-25 Statistical Calculations
2 Verification Data -Excavation (EXC)

Sample Area	Sample Number	Sample Date	TPH - Diesel Range Extended			Benzo(a)anthracene			Benzo(a)pyrene			Benzo(b)fluoranthene			Benzo(k)fluoranthene			Chrysene			Fluoranthene			Pyrene		
			ug/kg	Q	PQL	ug/kg	Q	PQL	ug/kg	Q	PQL	ug/kg	Q	PQL	ug/kg	Q	PQL	ug/kg	Q	PQL	ug/kg	Q	PQL	ug/kg	Q	PQL
EXC-4	J1PVP0	7/24/12	3300	J	960	3.1	U	3.1	6.2	U	6.2	4.1	U	4.1	3.8	U	3.8	4.7	U	4.7	13	U	13	12	U	12
Duplicate of J1PVP0	J1PVP9	7/24/12	2800	J	1000	3.1	U	3.1	6.2	U	6.2	4.0	U	4.0	3.8	U	3.8	4.6	U	4.6	12	U	12	12	U	12
EXC-1	J1PVN7	7/24/12	5000		1000	3.2	U	3.2	6.5	U	6.5	4.3	U	4.3	4.0	U	4.0	4.9	U	4.9	13	U	13	12	U	12
EXC-2	J1PVN8	7/24/12	950	U	950	3.1	U	3.1	6.2	U	6.2	4.1	U	4.1	3.8	U	3.8	4.7	U	4.7	13	U	13	12	U	12
EXC-3	J1PVN9	7/24/12	7000		980	110		3.3	80		6.6	90		4.3	31		4.1	110		5.0	180		13	180		12
EXC-5	J1PVP1	7/24/12	1500	J	1000	3.1	U	3.1	6.3	U	6.3	4.1	U	4.1	3.9	U	3.9	4.8	U	4.8	13	U	13	12	U	12
EXC-6	J1PVP2	7/24/12	8700		960	61		3.1	46		6.3	69		4.1	22		3.9	71		4.8	100		13	83		12
EXC-7	J1PVP3	7/24/12	5500		980	19	X	3.0	22		6.1	26		4.0	12	J	3.7	26	J	4.6	39		12	50		11
EXC-8	J1PVP4	7/24/12	1500	J	1000	3.2	U	3.2	6.5	U	6.5	4.3	U	4.3	4.0	U	4.0	4.9	U	4.9	13	U	13	12	U	12
EXC-9	J1PVP5	7/24/12	5600		960	7.5	J	3.0	8.7	JX	5.9	11	JX	3.9	6.4	J	3.7	9.8	J	4.5	18	J	12	15	J	11
EXC-10	J1PVP6	7/24/12	11000		930	110		3.0	100		5.9	120		3.9	46		3.6	140		4.5	210		12	250		11
EXC-11	J1PVP7	7/24/12	3100	J	940	5.0	JX	3.2	13	J	6.4	13	J	4.2	6.0	J	4.0	17	J	4.9	28	J	13	30	J	12
EXC-12	J1PVP8	7/24/12	14000		920	3.0	U	3.0	11	J	6.1	14	X	4.0	5.7	J	3.7	13	J	4.6	18	J	12	22	J	11

19 Statistical Computation Input Data

Sample Area	Sample Number	Sample Date	TPH - Diesel Range Extended		Benzo(a)anthracene		Benzo(a)pyrene		Benzo(b)fluoranthene		Benzo(k)fluoranthene		Chrysene		Fluoranthene		Pyrene	
			ug/kg		ug/kg		ug/kg		ug/kg		ug/kg		ug/kg		ug/kg		ug/kg	
EXC-4	J1PVP0/J1PVP9	7/24/12	3050		1.6		3.1		2.0		1.9		2.3		6.3		6.0	
EXC-1	J1PVN7	7/24/12	5000		1.6		3.3		2.2		2.0		2.5		6.5		6.0	
EXC-2	J1PVN8	7/24/12	475		1.6		3.1		2.1		1.9		2.4		6.5		6.0	
EXC-3	J1PVN9	7/24/12	7000		110		80		90		31		110		180		180	
EXC-5	J1PVP1	7/24/12	1500		1.6		3.2		2.1		2.0		2.4		6.5		6.0	
EXC-6	J1PVP2	7/24/12	8700		61		46		69		22		71		100		83	
EXC-7	J1PVP3	7/24/12	5500		19		22		26		12		26		39		50	
EXC-8	J1PVP4	7/24/12	1500		1.6		3.3		2.2		2.0		2.5		6.5		6.0	
EXC-9	J1PVP5	7/24/12	5600		7.5		8.7		11		6.4		9.8		18		15	
EXC-10	J1PVP6	7/24/12	11000		110		100		120		46		140		210		250	
EXC-11	J1PVP7	7/24/12	3100		5.0		13		13		6.0		17		28		30	
EXC-12	J1PVP8	7/24/12	14000		1.5		11		14		5.7		13		18		22	

34 Statistical Computations

		TPH - Diesel Range Extended		Benzo(a)anthracene		Benzo(a)pyrene		Benzo(b)fluoranthene		Benzo(k)fluoranthene		Chrysene		Fluoranthene		Pyrene	
95% UCL based on	N	Large data set (n ≥10), use MTCStat lognormal distribution.		Large data set (n ≥10), lognormal and normal distribution rejected, use z-statistic.		Large data set (n ≥10), lognormal and normal distribution rejected, use z-statistic.		Large data set (n ≥10), lognormal and normal distribution rejected, use z-statistic.		Large data set (n ≥10), lognormal and normal distribution rejected, use z-statistic.		Large data set (n ≥10), lognormal and normal distribution rejected, use z-statistic.		Large data set (n ≥10), lognormal and normal distribution rejected, use z-statistic.		Large data set (n ≥10), lognormal and normal distribution rejected, use z-statistic.	
% < Detection limit	8%	12		50%		42%		42%		42%		42%		42%		42%	
Mean	5535	27		25		29		12		33		52		72		80	
Standard deviation	4093	42		33		40		14		47		86		93			
95% UCL on mean	14657	47		40		49		18		56		210		250			
Maximum value	14000	110		100		120		46		140		210		250			
Most Stringent Cleanup Limit for nonradionuclide and RAG type (ug/kg)		200000 ug/kg	GW & River Protection	15 ug/kg	GW & River Protection	15 ug/kg	GW & River Protection	15 ug/kg	GW & River Protection	15 ug/kg	River Protection	100 ug/kg	River Protection	18000 ug/kg	River Protection	48000 ug/kg	GW Protection
WAC 173-340 3-PART TEST																	
95% UCL > Cleanup Limit?		NO		YES		YES		YES		YES		NO		NO		NO	
> 10% above Cleanup Limit?		NO		YES		YES		YES		YES		YES		NO		NO	
Any sample > 2X Cleanup Limit?		NO		YES		YES		YES		YES		NO		NO		NO	
WAC 173-340 Compliance?		The data set meets the 3-part test criteria when compared to the most stringent RAG.		A detailed assessment will be performed. The data set meets the 3-part test criteria when compared to the direct exposure RAG.		A detailed assessment will be performed. The data set meets the 3-part test criteria when compared to the direct exposure RAG.		A detailed assessment will be performed. The data set meets the 3-part test criteria when compared to the direct exposure RAG.		A detailed assessment will be performed. The data set meets the 3-part test criteria when compared to the direct exposure RAG.		A detailed assessment will be performed. The data set meets the 3-part test criteria when compared to the direct exposure RAG.		The data set meets the 3-part test criteria when compared to the most stringent RAG.		The data set meets the 3-part test criteria when compared to the most stringent RAG.	

Qualifiers are defined on sheet 3

Washington Closure HanfordOriginator J. D. SkoglieProject 100-N Field RemediationSubject 100-N-25 Waste Sites Cleanup Verification 95% UCL Calculations**MAXIMUM VALUE 3-PART TEST CALCULATION SHEET**Date 10/15/12
Job No. 14655Calc. No. 0100N-CA-V0151
Checked C. H. DobieRev. No. 0
Date 10/15/12
Sheet No. 8 of 13**1 100-N-25 Maximum Calculations****2 Verification Data -Excavation (EXC)**

Sample	Sample	Sample	Molybdenum			Acenaphthene			Anthracene			Benzo(ghi)perylene			Dibenz(a,h)anthracene			Fluorene			Indeno(1,2,3-cd)pyrene			Phenanthrene		
Area	Number	Date	mg/kg	Q	PQL	ug/kg	Q	PQL	ug/kg	Q	PQL	ug/kg	Q	PQL	ug/kg	Q	PQL	ug/kg	Q	PQL	ug/kg	Q	PQL	ug/kg	Q	PQL
EX-4	J1PVP0	7/24/12	0.24	U	0.24	9.7	U	9.7	2.9	U	2.9	7.0	U	7.0	11	U	11	5.1	U	5.1	12	U	12	12	U	12
Duplicate of J1PVP0	J1PVP9	7/24/12	0.25	U	0.25	9.6	U	9.6	2.9	U	2.9	6.9	U	6.9	11	U	11	5.1	U	5.1	12	U	12	12	U	12
EX-1	J1PVN7	7/24/12	0.36	B	0.26	10	U	10	3.1	U	3.1	7.3	U	7.3	11	U	11	5.4	U	5.4	12	U	12	12	U	12
EX-2	J1PVN8	7/24/12	0.33	B	0.24	9.6	U	9.6	2.9	U	2.9	6.9	U	6.9	11	U	11	5.1	U	5.1	12	U	12	12	U	12
EX-3	J1PVN9	7/24/12	0.26	U	0.26	17	JX	10	27		3.1	57		7.4	11	U	11	16	JX	5.4	52		12	88		12
EX-5	J1PVP1	7/24/12	0.23	U	0.23	9.8	U	9.8	3.0	U	3.0	7.1	U	7.1	11	U	11	5.2	U	5.2	12	U	12	12	U	12
EX-6	J1PVP2	7/24/12	0.23	U	0.23	9.9	U	9.9	11	J	3.0	39		7.1	11	U	11	8.8	J	5.2	40		12	31	J	12
EX-7	J1PVP3	7/24/12	0.22	U	0.22	9.5	U	9.5	2.9	U	2.9	18	J	6.8	10	U	10	5.0	U	5.0	15	J	11	11	U	11
EX-8	J1PVP4	7/24/12	0.24	U	0.24	10	U	10	3.1	U	3.1	7.3	U	7.3	11	U	11	5.4	U	5.4	12	U	12	12	U	12
EX-9	J1PVP5	7/24/12	0.26	U	0.26	9.3	U	9.3	2.8	U	2.8	6.7	U	6.7	10	U	10	4.9	U	4.9	11	U	11	11	U	11
EX-10	J1PVP6	7/24/12	0.25	U	0.25	22	JX	9.3	27		2.8	52	X	6.7	29		10	18	JX	4.9	67		11	94		11
EX-11	J1PVP7	7/24/12	0.25	U	0.25	10	U	10	3.1	U	3.1	7.2	U	7.2	11	U	11	5.3	U	5.3	12	U	12	12	J	12
EX-12	J1PVP8	7/24/12	0.24	U	0.24	9.5	U	9.5	2.9	U	2.9	9.1	J	6.9	10	U	10	5.0	U	5.0	11	U	11	11	U	11

3 Statistical Computations

	Molybdenum			Acenaphthene			Anthracene			Benzo(ghi)perylene			Dibenz(a,h)anthracene			Fluorene			Indeno(1,2,3-cd)pyrene			Phenanthrene		
% < Detection limit	83%			83%			75%			58%			92%			75%			67%			67%		
Maximum value	0.36			22			27			57			29			18			67			94		
Most Stringent Cleanup Limit for nonradionuclide and RAG type (mg/kg) unless otherwise noted	8 GW Protection			96000 ug/kg GW Protection			240000 ug/kg GW Protection			48000 ug/kg GW Protection			30 ug/kg GW & River Protection			64000 ug/kg GW Protection			15 ug/kg GW & River Protection			240000 ug/kg GW Protection		
3-PART TEST																								
Maximum > Cleanup Limit?	NO			NO			NO			NO			NO			NO			YES			NO		
> 10% above Cleanup Limit?	NO			NO			NO			NO			NO			NO			YES			NO		
Any sample > 2X Cleanup Limit?	NO			NO			NO			NO			NO			NO			YES			NO		
3-Part Test Compliance?	The data set meets the 3-part test criteria when compared to the most stringent RAG.			The data set meets the 3-part test criteria when compared to the most stringent RAG.			The data set meets the 3-part test criteria when compared to the most stringent RAG.			The data set meets the 3-part test criteria when compared to the most stringent RAG.			The data set meets the 3-part test criteria when compared to the most stringent RAG.			The data set meets the 3-part test criteria when compared to the most stringent RAG.			A detailed assessment will be performed. The data set meets the 3-part test criteria when compared to the direct exposure RAG.			The data set meets the 3-part test criteria when compared to the most stringent RAG.		

28 Qualifiers are defined on sheet 3

Washington Closure Hanford
Originator J. D. Skoglie
Project 100-N Field Remediation
Subject 100-N-25 Waste Sites Cleanup Verification 95% UCL Calculations

CALCULATION SHEET

Date 09/12/12
Job No. 14655

Calc. No. 0100N-CA-V0151
Checked C. H. Dobie

Rev. No. 0
Date 09/12/12
Sheet No. 9 of 13

Ecology Software (MTCASat) Results, 100-N-25 Excavation (EXC)

DATA	ID	Antimony 95% UCL Calculation				DATA	ID	Arsenic 95% UCL Calculation				DATA	ID	Barium 95% UCL Calculation			
0.79	J1PVP0/ J1PVP9					2.2	J1PVP0/ J1PVP9					58.0	J1PVP0/ J1PVP9				
1.6	J1PVN7					1.8	J1PVN7					80.2	J1PVN7				
1.0	J1PVN8	Number of samples	Uncensored values			1.8	J1PVN8	Number of samples	Uncensored values			57.1	J1PVN8	Number of samples	Uncensored values		
0.63	J1PVN9	Uncensored	12	Mean	0.84	1.6	J1PVN9	Uncensored	12	Mean	1.8	58.0	J1PVN9	Uncensored	12	Mean	57.1
0.99	J1PVP1	Censored		Lognormal mean	0.84	2.3	J1PVP1	Censored		Lognormal mean	1.8	44.1	J1PVP1	Censored		Lognormal mean	57.1
1.0	J1PVP2	Detection limit or PQL		Std. devn.	0.29	1.0	J1PVP2	Detection limit or PQL		Std. devn.	0.46	54.6	J1PVP2	Detection limit or PQL		Std. devn.	9.1
0.64	J1PVP3	Method detection limit		Median	0.76	1.9	J1PVP3	Method detection limit		Median	1.8	61.2	J1PVP3	Method detection limit		Median	56.0
0.89	J1PVP4	TOTAL	12	Min.	0.52	2.6	J1PVP4	TOTAL	12	Min.	0.99	49.1	J1PVP4	TOTAL	12	Min.	44.1
0.66	J1PVP5			Max.	1.6	1.7	J1PVP5			Max.	2.6	54.7	J1PVP5			Max.	80.2
0.52	J1PVP6					1.8	J1PVP6					63.8	J1PVP6				
0.68	J1PVP7					1.9	J1PVP7					49.1	J1PVP7				
0.73	J1PVP8					0.99	J1PVP8					54.8	J1PVP8				
		Lognormal distribution?	Normal distribution?					Lognormal distribution?	Normal distribution?					Lognormal distribution?	Normal distribution?		
		r-squared is: 0.920	r-squared is: 0.815					r-squared is: 0.860	r-squared is: 0.923					r-squared is: 0.913	r-squared is: 0.862		
		Recommendations:						Recommendations:						Recommendations:			
		Use lognormal distribution.						Use normal distribution.						Use lognormal distribution.			
		UCL (Land's method) is	1.0					UCL (based on t-statistic) is	2.0					UCL (Land's method) is	62.0		
DATA	ID	Beryllium 95% UCL Calculation				DATA	ID	Boron 95% UCL Calculation				DATA	ID	Cadmium 95% UCL Calculation			
0.21	J1PVP0/ J1PVP9					0.79	J1PVP0/ J1PVP9					0.12	J1PVP0/ J1PVP9				
0.22	J1PVN7					1.8	J1PVN7					0.15	J1PVN7				
0.21	J1PVN8	Number of samples	Uncensored values			1.5	J1PVN8	Number of samples	Uncensored values			0.14	J1PVN8	Number of samples	Uncensored values		
0.14	J1PVN9	Uncensored	12	Mean	0.17	1.0	J1PVN9	Uncensored	12	Mean	0.96	0.13	J1PVN9	Uncensored	12	Mean	0.13
0.16	J1PVP1	Censored		Lognormal mean	0.17	0.44	J1PVP1	Censored		Lognormal mean	0.98	0.12	J1PVP1	Censored		Lognormal mean	0.13
0.070	J1PVP2	Detection limit or PQL		Std. devn.	0.049	0.43	J1PVP2	Detection limit or PQL		Std. devn.	0.48	0.12	J1PVP2	Detection limit or PQL		Std. devn.	0.014
0.19	J1PVP3	Method detection limit		Median	0.16	1.1	J1PVP3	Method detection limit		Median	0.98	0.14	J1PVP3	Method detection limit		Median	0.13
0.25	J1PVP4	TOTAL	12	Min.	0.070	0.46	J1PVP4	TOTAL	12	Min.	0.43	0.10	J1PVP4	TOTAL	12	Min.	0.10
0.14	J1PVP5			Max.	0.25	1.6	J1PVP5			Max.	1.8	0.14	J1PVP5			Max.	0.15
0.16	J1PVP6					1.0	J1PVP6					0.12	J1PVP6				
0.15	J1PVP7					0.96	J1PVP7					0.12	J1PVP7				
0.13	J1PVP8					0.46	J1PVP8					0.14	J1PVP8				
		Lognormal distribution?	Normal distribution?					Lognormal distribution?	Normal distribution?					Lognormal distribution?	Normal distribution?		
		r-squared is: 0.876	r-squared is: 0.956					r-squared is: 0.908	r-squared is: 0.917					r-squared is: 0.906	r-squared is: 0.917		
		Recommendations:						Recommendations:						Recommendations:			
		Use normal distribution.						Use lognormal distribution.						Use lognormal distribution.			
		UCL (based on t-statistic) is	0.19					UCL (Land's method) is	1.4					UCL (Land's method) is	0.14		
DATA	ID	Chromium 95% UCL Calculation				DATA	ID	Cobalt 95% UCL Calculation				DATA	ID	Copper 95% UCL Calculation			
8.1	J1PVP0/ J1PVP9					8.5	J1PVP0/ J1PVP9					16.4	J1PVP0/ J1PVP9				
13.6	J1PVN7					8.5	J1PVN7					15.5	J1PVN7				
9.3	J1PVN8	Number of samples	Uncensored values			8.7	J1PVN8	Number of samples	Uncensored values			16.3	J1PVN8	Number of samples	Uncensored values		
6.7	J1PVN9	Uncensored	12	Mean	8.8	9.1	J1PVN9	Uncensored	12	Mean	8.9	15.7	J1PVN9	Uncensored	12	Mean	15.9
7.3	J1PVP1	Censored		Lognormal mean	8.8	8.4	J1PVP1	Censored		Lognormal mean	8.9	14.1	J1PVP1	Censored		Lognormal mean	15.9
8.1	J1PVP2	Detection limit or PQL		Std. devn.	1.8	11.1	J1PVP2	Detection limit or PQL		Std. devn.	0.79	17.6	J1PVP2	Detection limit or PQL		Std. devn.	1.1
10.0	J1PVP3	Method detection limit		Median	8.4	8.7	J1PVP3	Method detection limit		Median	8.8	15.9	J1PVP3	Method detection limit		Median	15.8
8.6	J1PVP4	TOTAL	12	Min.	6.7	9.4	J1PVP4	TOTAL	12	Min.	7.9	16.3	J1PVP4	TOTAL	12	Min.	14.1
7.7	J1PVP5			Max.	13.6	8.9	J1PVP5			Max.	11.1	14.1	J1PVP5			Max.	17.6
9.6	J1PVP6					7.9	J1PVP6					15.3	J1PVP6				
9.1	J1PVP7					9.1	J1PVP7					17.6	J1PVP7				
7.7	J1PVP8					8.9	J1PVP8					15.4	J1PVP8				
		Lognormal distribution?	Normal distribution?					Lognormal distribution?	Normal distribution?					Lognormal distribution?	Normal distribution?		
		r-squared is: 0.903	r-squared is: 0.825					r-squared is: 0.822	r-squared is: 0.780					r-squared is: 0.939	r-squared is: 0.941		
		Recommendations:						Recommendations:						Recommendations:			
		Use lognormal distribution.						Reject BOTH lognormal and normal distributions.						Use lognormal distribution.			
		UCL (Land's method) is	9.8					UCL (based on Z-statistic) is	9.3					UCL (Land's method) is	16.5		

Washington Closure Hanford

Originator J. D. Skoglie

Project 100-N Field Remediation

Subject 100-N-25 Waste Sites Cleanup Verification 95% UCL Calculations

CALCULATION SHEET

Date 09/12/12
Job No. 14655Calc. No. 0100N-CA-V0151
Checked C. H. DobieRev. No. 0
Date 09/12/12
Sheet No. 10 of 13

Ecology Software (MTCASat) Results, 100-N-25 Excavation (EXC)

DATA	ID	Lead 95% UCL Calculation				DATA	ID	Manganese 95% UCL Calculation				DATA	ID	Nickel 95% UCL Calculation			
4.6	J1PVP0/ J1PVP9					318	J1PVP0/ J1PVP9					10.3	J1PVP0/ J1PVP9				
4.8	J1PVN7					347	J1PVN7					10.9	J1PVN7				
4.0	J1PVN8	Number of samples	Uncensored values			325	J1PVN8	Number of samples	Uncensored values			13.4	J1PVN8	Number of samples	Uncensored values		
5.2	J1PVN9	Uncensored	12	Mean	5.0	312	J1PVN9	Uncensored	12	Mean	321	9.9	J1PVN9	Uncensored	12	Mean	10.9
4.1	J1PVP1	Censored		Lognormal mean	5.0	304	J1PVP1	Censored		Lognormal mean	321	9.7	J1PVP1	Censored		Lognormal mean	10.9
6.7	J1PVP2	Detection limit or PQL		Std. devn.	1.0	309	J1PVP2	Detection limit or PQL		Std. devn.	16.6	11.7	J1PVP2	Detection limit or PQL		Std. devn.	1.4
6.7	J1PVP3	Method detection limit		Median	4.7	327	J1PVP3	Method detection limit		Median	317	11.3	J1PVP3	Method detection limit		Median	10.6
5.9	J1PVP4	TOTAL	12	Min.	3.9	358	J1PVP4	TOTAL	12	Min.	304	13.3	J1PVP4	TOTAL	12	Min.	9.0
4.3	J1PVP5			Max.	6.7	316	J1PVP5			Max.	358	10.3	J1PVP5			Max.	13.4
6.0	J1PVP6					311	J1PVP6					10.1	J1PVP6				
3.9	J1PVP7					317	J1PVP7					10.8	J1PVP7				
4.3	J1PVP8					304	J1PVP8					9.0	J1PVP8				
		Lognormal distribution?	Normal distribution?					Lognormal distribution?	Normal distribution?					Lognormal distribution?	Normal distribution?		
		r-squared is: 0.919	r-squared is: 0.898					r-squared is: 0.864	r-squared is: 0.850					r-squared is: 0.939	r-squared is: 0.913		
		Recommendations:						Recommendations:						Recommendations:			
		Use lognormal distribution.						Reject BOTH lognormal and normal distributions.						Use lognormal distribution.			
		UCL (Land's method) is	5.6					UCL (based on Z-statistic) is	329					UCL (Land's method) is	11.6		
54.5	J1PVP0/ J1PVP9					43.8	J1PVP0/ J1PVP9					3.1	J1PVP0/ J1PVP9				
54.6	J1PVN7					53.7	J1PVN7					3.5	J1PVN7				
57.3	J1PVN8	Number of samples	Uncensored values			45.6	J1PVN8	Number of samples	Uncensored values			6.7	J1PVN8	Number of samples	Uncensored values		
61.7	J1PVN9	Uncensored	12	Mean	59.9	48.5	J1PVN9	Uncensored	12	Mean	48.6	3.5	J1PVN9	Uncensored	12	Mean	12.6
52.5	J1PVP1	Censored		Lognormal mean	59.9	46.0	J1PVP1	Censored		Lognormal mean	48.6	7.6	J1PVP1	Censored		Lognormal mean	10.7
70.6	J1PVP2	Detection limit or PQL		Std. devn.	5.2	48.6	J1PVP2	Detection limit or PQL		Std. devn.	4.6	2.1	J1PVP2	Detection limit or PQL		Std. devn.	22.8
59.7	J1PVP3	Method detection limit		Median	60.0	47.3	J1PVP3	Method detection limit		Median	47.2	5.4	J1PVP3	Method detection limit		Median	5.9
60.3	J1PVP4	TOTAL	12	Min.	52.5	48.5	J1PVP4	TOTAL	12	Min.	43.8	6.4	J1PVP4	TOTAL	12	Min.	2.0
62.8	J1PVP5			Max.	70.6	61.1	J1PVP5			Max.	61.1	83.9	J1PVP5			Max.	83.9
57.2	J1PVP6					46.9	J1PVP6					10.3	J1PVP6				
66.1	J1PVP7					46.2	J1PVP7					16.3	J1PVP7				
61.4	J1PVP8					47.0	J1PVP8					2.0	J1PVP8				
		Lognormal distribution?	Normal distribution?					Lognormal distribution?	Normal distribution?					Lognormal distribution?	Normal distribution?		
		r-squared is: 0.974	r-squared is: 0.962					r-squared is: 0.769	r-squared is: 0.732					r-squared is: 0.868	r-squared is: 0.445		
		Recommendations:						Recommendations:						Recommendations:			
		Use lognormal distribution.						Reject BOTH lognormal and normal distributions.						Reject BOTH lognormal and normal distributions.			
		UCL (Land's method) is	62.7					UCL (based on Z-statistic) is	50.8					UCL (based on Z-statistic) is	23.4		
0.70	J1PVP0/ J1PVP9					2.4	J1PVP0/ J1PVP9					2.2	J1PVP0/ J1PVP9				
0.43	J1PVN7					1.5	J1PVN7					1.0	J1PVN7				
1.3	J1PVN8	Number of samples	Uncensored values			1.3	J1PVN8	Number of samples	Uncensored values			0.88	J1PVN8	Number of samples	Uncensored values		
0.86	J1PVN9	Uncensored	12	Mean	0.68	3.2	J1PVN9	Uncensored	12	Mean	6.7	2.9	J1PVN9	Uncensored	12	Mean	6.7
0.91	J1PVP1	Censored		Lognormal mean	0.69	7.1	J1PVP1	Censored		Lognormal mean	7.4	7.0	J1PVP1	Censored		Lognormal mean	11.1
0.41	J1PVP2	Detection limit or PQL		Std. devn.	0.31	0.91	J1PVP2	Detection limit or PQL		Std. devn.	7.7	0.15	J1PVP2	Detection limit or PQL		Std. devn.	8.2
1.0	J1PVP3	Method detection limit		Median	0.56	8.1	J1PVP3	Method detection limit		Median	3.1	8.2	J1PVP3	Method detection limit		Median	2.9
0.43	J1PVP4	TOTAL	12	Min.	0.41	15.0	J1PVP4	TOTAL	12	Min.	0.59	16.5	J1PVP4	TOTAL	12	Min.	0.15
0.42	J1PVP5			Max.	1.3	2.9	J1PVP5			Max.	26.8	2.9	J1PVP5			Max.	27.4
0.94	J1PVP6					10.2	J1PVP6					11.0	J1PVP6				
0.42	J1PVP7					26.8	J1PVP7					27.4	J1PVP7				
0.41	J1PVP8					0.59	J1PVP8					0.15	J1PVP8				
		Lognormal distribution?	Normal distribution?					Lognormal distribution?	Normal distribution?					Lognormal distribution?	Normal distribution?		
		r-squared is: 0.837	r-squared is: 0.842					r-squared is: 0.982	r-squared is: 0.766					r-squared is: 0.949	r-squared is: 0.786		
		Recommendations:						Recommendations:						Recommendations:			
		Reject BOTH lognormal and normal distributions.						Use lognormal distribution.						Use lognormal distribution.			
		UCL (based on Z-statistic) is	0.83					UCL (Land's method) is	23.7					UCL (Land's method) is	103		

Washington Closure Hanford

Originator J. D. Skoglie

Project 100-N Field Remediation

Subject 100-N-25 Waste Sites Cleanup Verification 95% UCL Calculations

CALCULATION SHEET

Date 09/12/12
Job No. 14655

Calc. No. 0100N-CA-V0151

Checked C. H. Dobie

Rev. No. 0
Date 09/12/12
Sheet No. 11 of 13

Ecology Software (MTCStat) Results, 100-N-25 Excavation (EXC)

DATA	ID	Sulfate 95% UCL Calculation				DATA	ID	TPH - Diesel Range 95% UCL Calculation				DATA	ID	TPH - Diesel Range Extended 95% UCL Calculation			
7.4	J1PVP0/					2300	J1PVP0/					3050	J1PVP0/				
12.7	J1PVP9					3900	J1PVP9					5000	J1PVP9				
15.8	J1PVN7					870	J1PVN7					475	J1PVN7				
18.1	J1PVN8	Number of samples	Uncensored values			4300	J1PVN8	Number of samples	Uncensored values			7000	J1PVN8	Number of samples	Uncensored values		
13.6	J1PVN9	Uncensored	12	Mean	15.3	1100	J1PVN9	Uncensored	12	Mean	3806	1500	J1PVN9	Uncensored	12	Mean	5535
3.7	J1PVP1	Censored		Lognormal mean	16.3	5400	J1PVP1	Censored		Lognormal mean	3938	8700	J1PVP1	Censored		Lognormal mean	6336
15.1	J1PVP2	Detection limit or PQL		Std. devn.	10.0	3400	J1PVP2	Detection limit or PQL		Std. devn.	3071	5500	J1PVP2	Detection limit or PQL		Std. devn.	4093
30.8	J1PVP3	Method detection limit		Median	14.4	1100	J1PVP3	Method detection limit		Median	3300	1500	J1PVP3	Method detection limit		Median	5250
8.3	J1PVP4	TOTAL	12	Min.	3.0	3200	J1PVP4	TOTAL	12	Min.	870	5600	J1PVP4	TOTAL	12	Min.	475
19.6	J1PVP5			Max.	35.9	6000	J1PVP5			Max.	12000	11000	J1PVP5			Max.	14000
35.9	J1PVP6					2100	J1PVP6					3100	J1PVP6				
3.0	J1PVP7					12000	J1PVP7					14000	J1PVP7				
	J1PVP8						J1PVP8						J1PVP8				
		Lognormal distribution?	Normal distribution?					Lognormal distribution?	Normal distribution?					Lognormal distribution?	Normal distribution?		
		r-squared is: 0.947	r-squared is: 0.923					r-squared is: 0.967	r-squared is: 0.808					r-squared is: 0.934	r-squared is: 0.940		
		Recommendations:						Recommendations:						Recommendations:			
		Use lognormal distribution.						Use lognormal distribution.						Use lognormal distribution.			
		UCL (Land's method) is	28.8					UCL (Land's method) is	7157					UCL (Land's method) is	14657		
DATA	ID	Benzo(a)anthracene 95% UCL Calculation				DATA	ID	Benzo(a)pyrene 95% UCL Calculation				DATA	ID	Benzo(b)fluoranthene 95% UCL Calculation			
1.6	J1PVP0/					3.1	J1PVP0/					2.0	J1PVP0/				
1.6	J1PVP9					3.3	J1PVP9					2.2	J1PVP9				
1.6	J1PVN7					3.1	J1PVN7					2.1	J1PVN7				
110	J1PVN8	Number of samples	Uncensored values			80	J1PVN8	Number of samples	Uncensored values			90	J1PVN8	Number of samples	Uncensored values		
1.6	J1PVN9	Uncensored	12	Mean	27	3.2	J1PVN9	Uncensored	12	Mean	25	2.1	J1PVN9	Uncensored	12	Mean	29
61	J1PVP1	Censored		Lognormal mean	32	46	J1PVP1	Censored		Lognormal mean	26	69	J1PVP1	Censored		Lognormal mean	37
19	J1PVP2	Detection limit or PQL		Std. devn.	42	22	J1PVP2	Detection limit or PQL		Std. devn.	33	26	J1PVP2	Detection limit or PQL		Std. devn.	40
1.6	J1PVP3	Method detection limit		Median	3.3	3.3	J1PVP3	Method detection limit		Median	10	2.2	J1PVP3	Method detection limit		Median	12
7.5	J1PVP4	TOTAL	12	Min.	1.5	8.7	J1PVP4	TOTAL	12	Min.	3.1	11	J1PVP4	TOTAL	12	Min.	2.0
110	J1PVP5			Max.	110	100	J1PVP5			Max.	100	120	J1PVP5			Max.	120
5.0	J1PVP6					13	J1PVP6					13	J1PVP6				
1.5	J1PVP7					11	J1PVP7					14	J1PVP7				
	J1PVP8						J1PVP8						J1PVP8				
		Lognormal distribution?	Normal distribution?					Lognormal distribution?	Normal distribution?					Lognormal distribution?	Normal distribution?		
		r-squared is: 0.811	r-squared is: 0.653					r-squared is: 0.880	r-squared is: 0.711					r-squared is: 0.878	r-squared is: 0.730		
		Recommendations:						Recommendations:						Recommendations:			
		Reject BOTH lognormal and normal distributions.						Reject BOTH lognormal and normal distributions.						Reject BOTH lognormal and normal distributions.			
		UCL (based on Z-statistic) is	47					UCL (based on Z-statistic) is	40					UCL (based on Z-statistic) is	49		
DATA	ID	Benzo(k)fluoranthene 95% UCL Calculation				DATA	ID	Chrysene 95% UCL Calculation				DATA	ID	Fluoranthene 95% UCL Calculation			
1.9	J1PVP0/					2.3	J1PVP0/					6.3	J1PVP0/				
2.0	J1PVP9					2.5	J1PVP9					6.5	J1PVP9				
1.9	J1PVN7					2.4	J1PVN7					6.5	J1PVN7				
31	J1PVN8	Number of samples	Uncensored values			110	J1PVN8	Number of samples	Uncensored values			6.5	J1PVN8	Number of samples	Uncensored values		
2.0	J1PVN9	Uncensored	12	Mean	12	2.4	J1PVN9	Uncensored	12	Mean	33	180	J1PVN9	Uncensored	12	Mean	52
22	J1PVP1	Censored		Lognormal mean	12	71	J1PVP1	Censored		Lognormal mean	40	6.5	J1PVP1	Censored		Lognormal mean	55
12	J1PVP2	Detection limit or PQL		Std. devn.	14	26	J1PVP2	Detection limit or PQL		Std. devn.	47	100	J1PVP2	Detection limit or PQL		Std. devn.	72
2.0	J1PVP3	Method detection limit		Median	5.9	2.5	J1PVP3	Method detection limit		Median	11	39	J1PVP3	Method detection limit		Median	18
6.4	J1PVP4	TOTAL	12	Min.	1.9	9.8	J1PVP4	TOTAL	12	Min.	2.3	6.5	J1PVP4	TOTAL	12	Min.	6.3
48	J1PVP5			Max.	46	140	J1PVP5			Max.	140	18	J1PVP5			Max.	210
6.0	J1PVP6					17	J1PVP6					210	J1PVP6				
5.7	J1PVP7					13	J1PVP7					28	J1PVP7				
	J1PVP8						J1PVP8					18	J1PVP8				
		Lognormal distribution?	Normal distribution?					Lognormal distribution?	Normal distribution?					Lognormal distribution?	Normal distribution?		
		r-squared is: 0.883	r-squared is: 0.735					r-squared is: 0.882	r-squared is: 0.711					r-squared is: 0.868	r-squared is: 0.692		
		Recommendations:						Recommendations:						Recommendations:			
		Reject BOTH lognormal and normal distributions.						Reject BOTH lognormal and normal distributions.						Reject BOTH lognormal and normal distributions.			
		UCL (based on Z-statistic) is	18					UCL (based on Z-statistic) is	56					UCL (based on Z-statistic) is	86		

Washington Closure Hanford

Originator J. D. Skoglie
Project 100-N Field Remediation
Subject 100-N-25 Waste Sites Cleanup Verification 95% UCL Calculations

Date 09/12/12
Job No. 14655

CALCULATION SHEET

Calc. No. 0100N-CA-V0151
Checked C. H. Dobie *CD*

Rev. No. 0
Date 09/12/12
Sheet No. 12 of 13

Ecology Software (MTCASat) Results, 100-N-25 Excavation (EXC)

1	DATA	ID	Pyrene 95% UCL Calculation			
2	6.0	J1PVP0/				
		J1PVP9				
3	6.0	J1PVN7				
4	6.0	J1PVN8	Number of samples		Uncensored values	
5	180	J1PVN9	Uncensored	12	Mean	55
6	6.0	J1PVP1	Censored		Lognormal mean	59
7	83	J1PVP2	Detection limit or PQL		Std. devn.	80
8	50	J1PVP3	Method detection limit		Median	19
9	6.0	J1PVP4	TOTAL	12	Min.	6.0
10	15	J1PVP5			Max.	250
11	250	J1PVP6				
12	30	J1PVP7				
13	22	J1PVP8				
14						
15			Lognormal distribution?		Normal distribution?	
16			r-squared is: 0.879		r-squared is: 0.682	
17			Recommendations:			
18			Reject BOTH lognormal and normal distributions.			
19						
20			UCL (based on Z-statistic) is	93		

CALCULATION SHEET

Washington Closure Hanford

Originator J. D. Skoglie

Project 100-N Field Remediation

Subject 100-N-25 Waste Sites Cleanup Verification 95% UCL Calculations

Date 09/12/12
Job No. 14655Calc. No. 0100N-CA-V0151
Checked C. H. DobieRev. No. 0
Date 09/12/12
Sheet No. 13 of 13

1 Duplicate Analysis - 100-N-25 Excavation (EXC)

Sampling Area	Sample Number	Sample Date	Aluminum			Antimony			Arsenic			Barium			Beryllium			Cadmium			Calcium			Chromium			Cobalt		
			mg/kg	Q	PQL	mg/kg	Q	PQL	mg/kg	Q	PQL	mg/kg	Q	PQL	mg/kg	Q	PQL	mg/kg	Q	PQL	mg/kg	Q	PQL	mg/kg	Q	PQL	mg/kg	Q	PQL
EXC-4	J1PVP0	7/24/12	7570	X	1.5	0.85	J	0.36	2.4		0.62	58.9	X	0.071	0.23		0.031	0.12	B	0.038	6400	JX	13.2	8.3	X	0.054	8.5	X	0.094
Duplicate of J1PVP0	J1PVP9	7/24/12	7700	X	1.5	0.72	J	0.37	1.9		0.64	57.1	X	0.074	0.19		0.032	0.11	B	0.040	7030	JX	13.7	7.8	X	0.056	8.4	X	0.097

6 Analysis:

Duplicate Analysis	TDL	5	0.6	10	2	0.2	0.2	100	1	2
	Both > PQL?	Yes (continue)	Yes (continue)	Yes (continue)	Yes (continue)	Yes (continue)	Yes (continue)	Yes (continue)	Yes (continue)	Yes (continue)
	Both >5xTDL?	Yes (calc RPD)	No-Stop (acceptable)	No-Stop (acceptable)	Yes (calc RPD)	No-Stop (acceptable)	No-Stop (acceptable)	Yes (calc RPD)	Yes (calc RPD)	No-Stop (acceptable)
	RPD	1.7%			3.1%			9.4%	6.2%	
	Difference > 2 TDL?	Not applicable	No - acceptable	No - acceptable	Not applicable	No - acceptable	No - acceptable	Not applicable	Not applicable	No - acceptable

13 Duplicate Analysis - 100-N-25 Excavation (EXC)

Sampling Area	HEIS Number	Sample Date	Copper			Iron			Lead			Magnesium			Manganese			Nickel			Potassium			Silicon			Sodium		
			mg/kg	Q	PQL	mg/kg	Q	PQL	mg/kg	Q	PQL	mg/kg	Q	PQL	mg/kg	Q	PQL	mg/kg	Q	PQL	mg/kg	Q	PQL	mg/kg	Q	PQL	mg/kg	Q	PQL
EXC-4	J1PVP0	7/24/12	16.1		0.20	21100	X	3.6	4.6		0.25	4670	X	3.5	322	X	0.094	10.3	X	0.12	1230		38.4	393	J	5.3	298		55.2
Duplicate of J1PVP0	J1PVP9	7/24/12	16.7		0.21	21400	X	3.7	4.5		0.26	4440	X	3.6	314	X	0.097	10.2	X	0.12	1200		39.9	409	J	5.5	363		57.4

18 Analysis:

Duplicate Analysis	TDL	1	5	5	75	5	4	400	2	50
	Both > PQL?	Yes (continue)	Yes (continue)	Yes (continue)	Yes (continue)	Yes (continue)	Yes (continue)	Yes (continue)	Yes (continue)	Yes (continue)
	Both >5xTDL?	Yes (calc RPD)	Yes (calc RPD)	No-Stop (acceptable)	Yes (calc RPD)	Yes (calc RPD)	No-Stop (acceptable)	No-Stop (acceptable)	Yes (calc RPD)	Yes (calc RPD)
	RPD	3.7%	1.4%		5.0%	2.5%			4.0%	19.7%
	Difference > 2 TDL?	Not applicable	Not applicable	No - acceptable	Not applicable	Not applicable	No - acceptable	No - acceptable	Not applicable	Not applicable

25 Duplicate Analysis - 100-N-25 Excavation (EXC)

Sampling Area	HEIS Number	Sample Date	Vanadium			Zinc			Chloride			Nitrogen in Nitrate			Nitrogen in Nitrite and Nitrate			Sulfate			TPH - Diesel Range			TPH - Diesel Range Extended		
			mg/kg	Q	PQL	mg/kg	Q	PQL	mg/kg	Q	PQL	mg/kg	Q	PQL	mg/kg	Q	PQL	mg/kg	Q	PQL	ug/kg	Q	PQL	ug/kg	Q	PQL
EXC-4	J1PVP0	7/24/12	53.5	X	0.088	44.3	X	0.37	3.2	B	1.9	2.5	J	0.31	2.3		0.29	7.5		1.7	2600	J	650	3300	J	960
Duplicate of J1PVP0	J1PVP9	7/24/12	55.4	X	0.091	43.3	X	0.39	2.9	B	2.0	2.2	JB	0.31	2.0		0.29	7.3		1.7	2000	J	690	2800	J	1000

30 Analysis:

Duplicate Analysis	TDL	2.5	1	2	0.75	0.75	5	5000	5000
	Both > PQL?	Yes (continue)	Yes (continue)	Yes (continue)	Yes (continue)	Yes (continue)	Yes (continue)	Yes (continue)	Yes (continue)
	Both >5xTDL?	Yes (calc RPD)	Yes (calc RPD)	No-Stop (acceptable)	No-Stop (acceptable)	No-Stop (acceptable)	No-Stop (acceptable)	No-Stop (acceptable)	No-Stop (acceptable)
	RPD	3.5%	2.3%						
	Difference > 2 TDL?	Not applicable	Not applicable	No - acceptable	No - acceptable	No - acceptable	No - acceptable	No - acceptable	No - acceptable

36 Qualifiers are defined on sheet 3

Attachment 1. 100-N-25 Waste Site Verification Sample Results (Metals).

SAMPLE LOCATION	HEIS Number	Sample Date	Aluminum		Antimony		Arsenic		Barium		Beryllium		Boron	
			mg/kg	Q	PQL	mg/kg	Q	PQL	mg/kg	Q	mg/kg	Q	mg/kg	Q
EXC-4	J1PVP0	7/24/12	7570	X	1.5	0.85	J	0.36	58.9	X	0.071	0.23	1.1	B
Duplicate of J1PVP0	J1PVP9	7/24/12	7700	X	1.5	0.72	J	0.37	57.1	X	0.074	0.19	0.95	U
EXC-1	J1PVP7	7/24/12	8530	X	1.6	1.6	JM	0.38	80.2	X	0.076	0.22	1.8	B
EXC-2	J1PVP8	7/24/12	7950	X	1.5	1.0	J	0.36	57.1	X	0.071	0.21	1.5	B
EXC-3	J1PVP9	7/24/12	5700	X	1.5	0.63	J	0.38	58.0	X	0.075	0.14	1.0	B
EXC-5	J1PVP1	7/24/12	6170	X	1.4	0.99	J	0.34	44.1	X	0.068	0.16	0.87	U
EXC-6	J1PVP2	7/24/12	6290	X	1.4	1.0	J	0.33	54.6	X	0.066	0.14	0.86	U
EXC-7	J1PVP3	7/24/12	7410	X	1.3	0.64	J	0.32	61.2	X	0.065	0.19	1.1	B
EXC-8	J1PVP4	7/24/12	8370	X	1.4	0.89	J	0.35	49.1	X	0.070	0.25	0.91	U
EXC-9	J1PVP5	7/24/12	6420	X	1.5	0.66	J	0.37	54.7	X	0.075	0.14	1.6	B
EXC-10	J1PVP6	7/24/12	7040	X	1.5	0.52	JB	0.37	63.8	X	0.074	0.16	1.0	B
EXC-11	J1PVP7	7/24/12	6820	X	1.5	0.68	J	0.37	49.1	X	0.074	0.15	0.96	B
EXC-12	J1PVP8	7/24/12	5800	X	1.4	0.73	J	0.35	54.8	X	0.070	0.13	0.91	U
Equipment Blank	J1PVR0	7/24/12	246	X	1.5	0.37	UJ	0.35	2.5	X	0.075	0.032	0.96	U

SAMPLE LOCATION	HEIS Number	Sample Date	Cadmium		Calcium		Chromium		Cobalt		Copper		Iron	
			mg/kg	Q	PQL	mg/kg	Q	PQL	mg/kg	Q	mg/kg	Q	mg/kg	Q
EXC-4	J1PVP0	7/24/12	0.12	B	0.038	6400	JX	13.2	8.5	X	0.094	0.20	21100	X
Duplicate of J1PVP0	J1PVP9	7/24/12	0.11	B	0.040	7030	JX	13.7	8.4	X	0.097	0.21	21400	X
EXC-1	J1PVP7	7/24/12	0.15	B	0.041	4950	JXM	14.2	8.5	X	0.10	0.22	22200	X
EXC-2	J1PVP8	7/24/12	0.14	B	0.038	5800	JX	13.2	8.7	X	0.094	0.20	22800	X
EXC-3	J1PVP9	7/24/12	0.13	B	0.041	8530	JX	14.0	9.1	X	0.099	0.22	22800	X
EXC-5	J1PVP1	7/24/12	0.12	B	0.037	6500	JX	12.6	8.4	X	0.089	0.19	21300	X
EXC-6	J1PVP2	7/24/12	0.12	B	0.036	6400	JX	12.3	11.1	X	0.44	0.95	23300	X
EXC-7	J1PVP3	7/24/12	0.14	B	0.035	5730	JX	10.0	8.7	X	0.085	0.18	22600	X
EXC-8	J1PVP4	7/24/12	0.10	B	0.038	7250	JX	13.1	9.4	X	0.093	0.20	23600	X
EXC-9	J1PVP5	7/24/12	0.14	B	0.040	5500	JX	13.9	8.9	X	0.099	0.21	23300	X
EXC-10	J1PVP6	7/24/12	0.12	B	0.040	6150	JX	13.8	7.9	X	0.098	0.21	20300	X
EXC-11	J1PVP7	7/24/12	0.12	B	0.040	7580	JX	13.7	9.1	X	0.098	0.21	23900	X
EXC-12	J1PVP8	7/24/12	0.14	B	0.038	5070	JX	13.0	8.9	X	0.093	0.20	22600	X
Equipment Blank	J1PVR0	7/24/12	0.040	U	0.040	46.1	JBX	0.17	0.11	BJX	0.098	0.21	291	X

Note: Data qualified with B, C, and/or J are considered acceptable values.

B = estimated result

C = $\leq 5\times$ blank concentration

HEIS = Hanford Environmental Information System

J = result < RL but \geq MDL and the concentration is an

approximate value.

M = sample duplicate not met

N = recovery outside control limits

PAH = polycyclic aromatic hydrocarbons

PQL = practical quantitation limit

Q = qualifier

U = undetected

X = $>40\%$ difference between columns, lower result reported (organics).

X = serial dilution indicates physical and chemical interferences present (metals).

Attachment

Originator

Checked

Calc. No.

Sheet No.

Date

Date

Rev. No.

1 of 4

Attachment 1. 100-N-25 Waste Site Verification Sample Results (Metals).

SAMPLE LOCATION	HEIS Number	Sample Date	Lead		Magnesium		Manganese		Mercury		Molybdenum		Nickel	
			mg/kg	Q	mg/kg	Q	mg/kg	Q	mg/kg	Q	mg/kg	Q	mg/kg	Q
EXC-4	J1PV0	7/24/12	4.6	0.25	4670	X	3.5	322	0.0047	U	0.24	0.24	10.3	X
Duplicate of J1PV0	J1PV9	7/24/12	4.5	0.26	4440	X	3.6	314	0.0054	U	0.25	0.25	10.2	X
EXC-1	J1PV7	7/24/12	4.8	0.27	4330	X	3.7	347	0.0064	U	0.26	0.26	10.9	X
EXC-2	J1PV8	7/24/12	4.0	0.25	4970	X	3.5	325	0.0056	U	0.24	0.24	13.4	X
EXC-3	J1PV9	7/24/12	5.2	0.27	4540	X	3.7	312	0.0066	U	0.26	0.26	9.9	X
EXC-5	J1PV1	7/24/12	4.1	0.24	4890	X	3.3	304	0.0054	U	0.23	0.23	9.7	X
EXC-6	J1PV2	7/24/12	6.7	1.2	4600	X	3.2	309	0.0052	U	0.23	0.23	11.7	X
EXC-7	J1PV3	7/24/12	6.7	0.23	4470	X	3.1	327	0.0053	U	0.22	0.22	11.3	X
EXC-8	J1PV4	7/24/12	5.9	0.25	5820	X	3.4	358	0.0051	U	0.24	0.24	13.3	X
EXC-9	J1PV5	7/24/12	4.3	0.27	4470	X	3.6	316	0.0049	U	0.26	0.26	10.3	X
EXC-10	J1PV6	7/24/12	6.0	0.26	4230	X	3.6	311	0.0067	U	0.25	0.25	10.1	X
EXC-11	J1PV7	7/24/12	3.9	0.26	4900	X	3.6	317	0.0059	U	0.25	0.25	10.8	X
EXC-12	J1PV8	7/24/12	4.3	0.25	3870	X	3.4	304	0.0049	U	0.24	0.24	9.0	X
Equipment Blank	J1PV0	7/24/12	0.48	B	0.26	28.6	X	5.1	0.0059	U	0.25	0.25	0.17	BX

SAMPLE LOCATION	HEIS Number	Sample Date	Potassium		Selenium		Silicon		Silver		Sodium		Vanadium	
			mg/kg	Q	mg/kg	Q	mg/kg	Q	mg/kg	Q	mg/kg	Q	mg/kg	Q
EXC-4	J1PV0	7/24/12	1230	38.4	0.80	U	0.80	393	5.3	0.15	298	55.2	53.5	X
Duplicate of J1PV0	J1PV9	7/24/12	1200	39.9	0.84	U	0.84	409	5.5	0.16	363	57.4	55.4	X
EXC-1	J1PV7	7/24/12	1680	41.2	0.86	U	0.86	444	5.7	0.16	300	59.3	54.6	X
EXC-2	J1PV8	7/24/12	1250	38.5	0.81	U	0.81	540	5.3	0.15	314	55.3	57.3	X
EXC-3	J1PV9	7/24/12	802	40.7	0.85	U	0.85	230	5.6	0.16	347	58.5	61.7	X
EXC-5	J1PV1	7/24/12	928	36.6	0.77	U	0.77	278	5.0	0.14	297	52.6	52.5	X
EXC-6	J1PV2	7/24/12	893	35.8	0.73	U	0.73	299	4.9	0.14	396	51.5	70.6	X
EXC-7	J1PV3	7/24/12	1230	34.9	0.73	U	0.73	323	4.8	0.14	318	50.2	59.7	X
EXC-8	J1PV4	7/24/12	1280	36.0	0.80	U	0.80	282	5.2	0.15	359	54.7	60.3	X
EXC-9	J1PV5	7/24/12	967	40.4	0.85	U	0.85	325	5.6	0.16	333	58.2	62.8	X
EXC-10	J1PV6	7/24/12	1110	40.2	0.84	U	0.84	403	5.5	0.16	347	57.8	57.2	X
EXC-11	J1PV7	7/24/12	1010	40.0	0.84	U	0.84	354	5.5	0.16	339	57.5	66.1	X
EXC-12	J1PV8	7/24/12	919	37.9	0.80	U	0.80	299	5.2	0.15	312	54.6	61.4	X
Equipment Blank	J1PV0	7/24/12	55.8	B	0.42	0.84	U	136	5.5	0.16	57.8	57.8	0.33	BX

SAMPLE LOCATION	HEIS Number	Sample Date	Zinc	
			mg/kg	Q
EXC-4	J1PV0	7/24/12	44.3	X
Duplicate of J1PV0	J1PV9	7/24/12	43.3	X
EXC-1	J1PV7	7/24/12	53.7	X
EXC-2	J1PV8	7/24/12	45.6	X
EXC-3	J1PV9	7/24/12	48.5	X
EXC-5	J1PV1	7/24/12	46.0	X
EXC-6	J1PV2	7/24/12	48.6	X
EXC-7	J1PV3	7/24/12	47.3	X
EXC-8	J1PV4	7/24/12	48.5	X
EXC-9	J1PV5	7/24/12	61.1	X
EXC-10	J1PV6	7/24/12	46.9	X
EXC-11	J1PV7	7/24/12	46.2	X
EXC-12	J1PV8	7/24/12	47.0	X
Equipment Blank	J1PV0	7/24/12	1.5	U/CX

Attachment
Originator
Checked
Calc. No.J. D. Skoglie
C. H. Dobie
0100N-CA-V0151Sheet No.
Date
Rev. No.2 of 4
9/12/2012
9/12/2012
0

Attachment 1. 100-N-25 Waste Site Verification Sample Results (Anions and TPH).

SAMPLE LOCATION	HEIS Number	Sample Date	Bromide		Chloride		Fluoride		Nitrogen in Nitrate		Nitrogen in Nitrite		Nitrogen in Nitrite and Nitrate	
			mg/kg	Q	mg/kg	Q	mg/kg	Q	mg/kg	Q	mg/kg	Q	mg/kg	Q
EXC-4	J1PVP0	7/24/12	0.38	U	0.38	B	1.9	0.99	0.81	2.5	0.31	0.33	2.3	0.29
Duplicate of J1PVP0	J1PVP9	7/24/12	0.39	U	0.39	B	2.0	0.82	0.82	2.2	0.31	0.34	2.0	0.29
EXC-1	J1PVP7	7/24/12	0.40	U	0.40	B	2.0	0.85	0.85	1.5	0.33	0.35	1.0	0.31
EXC-2	J1PVP8	7/24/12	0.39	U	0.39	B	2.0	0.82	0.82	1.3	0.33	0.33	0.88	0.30
EXC-3	J1PVP9	7/24/12	0.39	U	0.39	B	2.0	0.86	0.83	3.2	0.32	0.34	2.9	0.30
EXC-5	J1PVP1	7/24/12	0.39	U	0.39	B	2.0	0.91	0.84	7.1	0.32	0.34	7.0	0.30
EXC-6	J1PVP2	7/24/12	0.39	U	0.39	B	2.0	0.82	0.82	0.91	0.31	0.34	0.29	0.29
EXC-7	J1PVP3	7/24/12	0.38	U	0.38	B	1.9	1.0	0.81	8.1	0.31	0.33	8.2	0.29
EXC-8	J1PVP4	7/24/12	0.79	B	0.40	B	2.0	0.85	0.85	15.0	0.32	0.35	16.5	0.31
EXC-9	J1PVP5	7/24/12	0.88	B	0.39	B	2.0	0.84	0.84	2.9	0.32	0.34	2.9	0.30
EXC-10	J1PVP6	7/24/12	0.38	U	0.38	B	1.9	0.94	0.81	10.2	0.31	0.33	11.0	0.30
EXC-11	J1PVP7	7/24/12	0.39	U	0.39	B	2.0	0.83	0.83	26.8	0.32	0.34	27.4	0.30
EXC-12	J1PVP8	7/24/12	0.38	U	0.38	B	1.9	0.81	0.81	0.59	0.31	0.33	0.30	0.30
Equipment Blank	J1PVR0	7/24/12												

SAMPLE LOCATION	HEIS Number	Sample Date	Orthophosphate		Sulfate		TPH - Diesel Range		TPH - Diesel Range Extended		Percent moisture (wet sample)		pH Measurement	
			mg/kg	Q	mg/kg	Q	ug/kg	Q	ug/kg	Q	%	Q	pH	Q
EXC-4	J1PVP0	7/24/12	1.2	U	1.2	1.7	2600	J	3300	J	1.0	0.10	9.06	J
Duplicate of J1PVP0	J1PVP9	7/24/12	1.2	U	1.2	1.7	2000	J	2800	J	1.2	0.10	8.99	J
EXC-1	J1PVP7	7/24/12	1.3	U	1.3	1.8	3900	J	5000	J	4.4	0.10	8.75	J
EXC-2	J1PVP8	7/24/12	1.2	U	1.2	1.7	870	J	950	U	1.3	0.10	9.04	J
EXC-3	J1PVP9	7/24/12	1.3	JB	1.3	1.7	4300	J	7000	J	3.0	0.10	9.07	J
EXC-5	J1PVP1	7/24/12	1.3	U	1.3	1.8	1100	J	1500	J	1.6	0.10	9.06	J
EXC-6	J1PVP2	7/24/12	1.2	U	1.2	1.7	5400	J	8700	J	1.2	0.10	9.08	J
EXC-7	J1PVP3	7/24/12	1.2	U	1.2	1.7	3400	J	5500	J	1.3	0.10	8.93	J
EXC-8	J1PVP4	7/24/12	1.3	U	1.3	1.8	1100	J	1500	J	3.7	0.10	8.87	J
EXC-9	J1PVP5	7/24/12	1.3	U	1.3	1.8	3200	J	5600	J	1.6	0.10	8.60	J
EXC-10	J1PVP6	7/24/12	1.2	U	1.2	1.7	6000	J	11000	J	0.89	0.10	8.73	J
EXC-11	J1PVP7	7/24/12	1.2	U	1.2	1.7	2100	J	3100	J	1.4	0.10	8.63	J
EXC-12	J1PVP8	7/24/12	1.2	U	1.2	1.7	12000	J	14000	J	0.87	0.10	8.96	J
Equipment Blank	J1PVR0	7/24/12									0.10	U	0.10	

Attachment 1

Originator
Checked
Calc. No.

J. D. Stogdole
C. H. Dobie
0100N-CA-V0151

Date
Date
Rev. No.

9/12/2012
9/12/2012
0

3 of 4

Attachment 1. 100-N-25 Waste Site Verification Sample Results (Organics)

CONSTITUENT	CLASS	EXC-4 - J1PVP0										Duplicate of J1PVP0 - J1PVP9										EXC-1 - J1PVP7										EXC-2 - J1PVP8										EXC-3 - J1PVP9										EXC-5 - J1PVP1										EXC-6 - J1PVP2									
		7/24/12					7/24/12					7/24/12					7/24/12					7/24/12					7/24/12					7/24/12					7/24/12					7/24/12					7/24/12					7/24/12																			
		ug/kg	Q	PQL	ug/kg	Q	PQL	ug/kg	Q	PQL	ug/kg	Q	PQL	ug/kg	Q	PQL	ug/kg	Q	PQL	ug/kg	Q	PQL	ug/kg	Q	PQL	ug/kg	Q	PQL	ug/kg	Q	PQL	ug/kg	Q	PQL	ug/kg	Q	PQL	ug/kg	Q	PQL																															
Acenaphthene	PAH	9.7	U	9.7	U	9.6	U	9.6	U	10	9.6	U	9.6	U	9.6	U	10	9.6	U	9.6	U	9.6	U	17	JX	10	9.3	U	9.8	U	9.8	U	9.8	U	9.8	U	9.9	U	9.9	U																															
Acenaphthylene	PAH	8.7	U	8.7	U	8.6	U	8.6	U	9.2	U	9.2	U	8.7	U	8.7	U	9.2	U	8.7	U	8.7	U	9.3	U	9.3	U	8.9	U	8.9	U	8.9	U	8.9	U	8.9	U	8.9	U																																
Anthracene	PAH	2.9	U	2.9	U	2.9	U	2.9	U	3.1	U	3.1	U	2.9	U	2.9	U	3.1	U	2.9	U	2.9	U	27			3.1	U	3.0	U	3.0	U	3.0	U	3.0	U	3.0	U	3.0	U																															
Benzofluoranthene	PAH	3.1	U	3.1	U	3.1	U	3.1	U	3.2	U	3.2	U	3.1	U	3.1	U	3.2	U	3.1	U	3.1	U	110			3.3	U	3.1	U	3.1	U	3.1	U	3.1	U	3.1	U	3.1	U																															
Benzofluorene	PAH	6.2	U	6.2	U	6.2	U	6.2	U	6.5	U	6.5	U	6.2	U	6.2	U	6.5	U	6.2	U	6.2	U	80			6.6	U	6.3	U	6.3	U	6.3	U	6.3	U	6.3	U	6.3	U																															
Benzofluoranthene	PAH	4.1	U	4.1	U	4.0	U	4.0	U	4.3	U	4.3	U	4.1	U	4.1	U	4.3	U	4.1	U	4.1	U	90			4.3	U	4.1	U	4.1	U	4.1	U	4.1	U	4.1	U	4.1	U																															
Benzofluorene	PAH	7.0	U	7.0	U	6.9	U	6.9	U	7.3	U	7.3	U	6.9	U	6.9	U	7.3	U	6.9	U	6.9	U	57			7.4	U	7.1	U	7.1	U	7.1	U	7.1	U	7.1	U	7.1	U																															
Benzofluoranthene	PAH	3.8	U	3.8	U	3.8	U	3.8	U	4.0	U	4.0	U	3.8	U	3.8	U	4.0	U	3.8	U	3.8	U	31			4.1	U	3.9	U	3.9	U	3.9	U	3.9	U	3.9	U	3.9	U																															
Chrysene	PAH	4.7	U	4.7	U	4.6	U	4.6	U	4.9	U	4.9	U	4.7	U	4.7	U	4.9	U	4.7	U	4.7	U	110			5.0	U	4.8	U	4.8	U	4.8	U	4.8	U	4.8	U	4.8	U																															
Dibenzofluoranthene	PAH	11	U	11	U	11	U	11	U	11	U	11	U	11	U	11	U	11	U	11	U	11	U	11	U	11	U	11	U	11	U	11	U	11	U	11	U	11	U																																
Fluoranthene	PAH	13	U	13	U	12	U	12	U	13	U	13	U	13	U	13	U	13	U	13	U	13	U	180			13	U	13	U	13	U	13	U	13	U	13	U	13	U																															
Fluorene	PAH	5.1	U	5.1	U	5.1	U	5.1	U	5.4	U	5.4	U	5.1	U	5.1	U	5.4	U	5.1	U	5.1	U	16			5.4	U	5.2	U	5.2	U	5.2	U	5.2	U	5.2	U	5.2	U																															
Indeno(1,2,3-cd)pyrene	PAH	12	U	12	U	12	U	12	U	12	U	12	U	12	U	12	U	12	U	12	U	12	U	52			12	U	12	U	12	U	12	U	12	U	12	U	12	U																															
Naphthalene	PAH	12	U	12	U	12	U	12	U	12	U	12	U	12	U	12	U	12	U	12	U	12	U	12	U	12	U	12	U	12	U	12	U	12	U	12	U	12	U																																
Phenanthrene	PAH	12	U	12	U	12	U	12	U	12	U	12	U	12	U	12	U	12	U	12	U	12	U	88			12	U	12	U	12	U	12	U	12	U	12	U	12	U																															
Pyrene	PAH	12	U	12	U	12	U	12	U	12	U	12	U	12	U	12	U	12	U	12	U	12	U	180			12	U	12	U	12	U	12	U	12	U	12	U	12	U																															

Acrobat 8.0

CALCULATION COVER SHEETProject Title: 100-N Field Remediation Job No. 14655Area: 100-NDiscipline: Environmental Calculation No: 0100N-CA-V0152Subject: 100-N-25 Waste Site Direct Contact Hazard Quotient and Carcinogenic Risk CalculationsComputer Program: Excel Program No: Excel 2003

The attached calculations have been generated to document compliance with established cleanup levels. These calculations should be used in conjunction with other relevant documents in the administrative record.

Committed Calculation ☒Preliminary ☐Superseded ☐Voided ☐

Rev.	Sheet Numbers	Originator	Checker	Reviewer	Approval	Date
0	Cover = 1 Summary = 3 Total = 4	J. D. Skoglie	C. H. Dobie	N. K. Schifferm	D. F. Obenauer	12/20/12
		<i>[Signature]</i>	<i>[Signature]</i>	<i>[Signature]</i>	<i>[Signature]</i>	

SUMMARY OF REVISION

--	--

WCH-DE-018 (05/08/2007)

DE01-437.03

Washington Closure Hanford, Inc.

CALCULATION SHEET

Originator:	J. D. Skoglie	Date:	10/15/2012	Calc. No.:	0100N-CA-V0152	Rev.:	0
Project:	100-N Field Remediation	Job No.:	14655	Checked:	C. H. Dobie	Date:	10/15/2012
Subject:	100-N-25 Waste Site Direct Contact Hazard Quotient and Carcinogenic Risk Calculations						Sheet No. 1 of 3

PURPOSE:

Provide documentation to support the calculation of the direct contact hazard quotient (HQ) and excess carcinogenic risk for the 100-N-25 waste site. In accordance with the remedial action goals (RAGs) in the remedial design report/remedial action work plan (RDR/RAWP) (DOE-RL 2006b), the following criteria must be met:

- 1) An HQ of <1.0 for all individual noncarcinogens
- 2) A cumulative HQ of <1.0 for noncarcinogens
- 3) An excess cancer risk of $<1 \times 10^{-6}$ for individual carcinogens
- 4) A cumulative excess cancer risk of $<1 \times 10^{-5}$ for carcinogens.

GIVEN/REFERENCES:

- 1) DOE-RL, 2006a, *100-N Area Sampling and Analysis Plan for CERCLA Waste Sites*, DOE/RL-2005-92, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington.
- 2) DOE-RL, 2006b, *Remedial Design Report/Remedial Action Work Plan for the 100-N Area*, DOE/RL-2005-93, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington
- 3) WAC 173-340, "Model Toxics Control Act – Cleanup," *Washington Administrative Code*, 1996.
- 4) WCH, 2012, *Remaining Sites Verification Package for the 100-N-25, French Drain 1 Liquid Waste Site*, Attachment to Waste Site Reclassification Form 2012-079, Washington Closure Hanford, Inc., Richland, Washington.

SOLUTION:

- 1) Generate an HQ for each noncarcinogenic constituent detected above background or required detection limit/practical quantitation limit and compare it to the individual HQ of <1.0 (DOE-RL 2006b).
- 2) Sum the HQs and compare this value to the cumulative HQ of <1.0 .
- 3) Generate an excess cancer risk value for each carcinogenic constituent detected above background or required detection limit/practical quantitation limit and compare it to the excess cancer risk of $<1 \times 10^{-6}$ (DOE-RL 2006b).
- 4) Sum the excess cancer risk value(s) and compare it to the cumulative cancer risk of $<1 \times 10^{-5}$.

Washington Closure Hanford, Inc.		CALCULATION SHEET				
Originator:	J. D. Skogle	Date:	10/15/2012	Calc. No.:	0100N-CA-V0152	Rev.: 0
Project:	100-N Field Remediation	Job No:	14655	Checked:	C. H. Dobie	Date: 10/15/2012
Subject:	100-N-25 Waste Site Direct Contact Hazard Quotient and Carcinogenic Risk Calculations					Sheet No. 2 of 3

METHODOLOGY:

The 100-N-25 waste site is comprised of one decision unit for verification sampling consisting of the excavation area. The direct contact hazard quotient and carcinogenic risk calculations for the 100-N-25 waste site was conservatively calculated for the entire waste site using the greater of the maximum or statistical verification soil sample results (WCH 2012). Of the contaminants of potential concern (COPCs) for this site, boron, molybdenum, and the detected polycyclic aromatic hydrocarbons (PAHs) require HQ and risk calculations because these analytes were detected and a Washington State or Hanford Site background value is not available. Nitrogen in nitrate and nitrite require HQ and risk calculations because this analyte was detected above the Washington State or Hanford Site background value. Although total petroleum hydrocarbons (diesel range extended) were detected and no background value is available, the risk associated with total petroleum hydrocarbons do not contribute to the cumulative toxicity calculation. All other site nonradionuclide COPCs were not detected or were quantified below background levels. An example of the HQ and risk calculations is presented below:

- 1) For example, the statistical value for boron is 1.4 mg/kg, divided by the noncarcinogenic RAG value of 16,000 mg/kg (calculated in accordance with the noncarcinogenic toxics effects formula in WAC 173-340-740[3]), is 8.8×10^{-5} . Comparing this value, and all other individual values, to the requirement of <1.0 , this criterion is met.
- 2) After the HQ calculation is completed for the appropriate analytes, the cumulative HQ can be obtained by summing the individual values. To avoid errors due to intermediate rounding, the individual HQ values prior to rounding are used for this calculation. The sum of the HQ values is 1.9×10^{-3} . Comparing this value to the requirement of <1.0 , this criterion is met.
- 3) To calculate the excess cancer risk, the maximum or statistical value is divided by the carcinogenic RAG value, then multiplied by 1.0×10^{-6} . For example, the statistical value for benzo(b)fluoranthene is 0.049 mg/kg, divided by 1.37 mg/kg, and multiplied as indicated, is 3.6×10^{-8} . Comparing this value, and all other individual values, to the requirement of $<1 \times 10^{-6}$, this criterion is met.
- 4) After these calculations are completed for the carcinogenic analytes, the cumulative excess cancer risk can be obtained by summing the individual values. To avoid errors due to intermediate rounding, the individual cancer risk values prior to rounding are used for this calculation. The sum of the excess cancer risk values is 6.2×10^{-7} . Comparing this value to the requirement of $<1 \times 10^{-5}$, this criterion is met.

RESULTS:

- 1) List individual noncarcinogens and corresponding HQs >1.0 : None
- 2) List the cumulative noncarcinogenic HQ >1.0 : None
- 3) List individual carcinogens and corresponding excess cancer risk $>1 \times 10^{-6}$: None
- 4) List the cumulative excess cancer risk for carcinogens $>1 \times 10^{-5}$: None

Table 1 shows the results of the hazard quotient and excess cancer risk calculations.

Washington Closure Hanford, Inc.

CALCULATION SHEET

Originator:	J. D. Skoglie	Date:	10/15/2012	Calc. No.:	0100N-CA-V0152	Rev.:	0
Project:	100-N Field Remediation	Job No:	14655	Checked:	C. H. Dobie	Date:	10/15/2012
Subject:	100-N-25 Waste Site Direct Contact Hazard Quotient and Carcinogenic Risk Calculations					Sheet No.	3 of 3

**Table 1. Direct Contact Hazard Quotient and Excess Cancer Risk Results
for the 100-N-25 Waste Site.**

Contaminants of Potential Concern	Maximum or Statistical Value ^a (mg/kg)	Noncarcinogen RAG ^b (mg/kg)	Hazard Quotient	Carcinogen RAG ^b (mg/kg)	Carcinogen Risk
Metals					
Boron	1.4	16,000	8.8E-05	--	--
Molybdenum	0.36	400	9.0E-04	--	--
Anions					
Nitrogen in nitrate and nitrite	103	128,000	8.0E-04	--	--
Polycyclic Aromatic Hydrocarbons					
Acenaphthene	0.022	4,800	4.6E-06	--	--
Anthracene	0.027	24,000	1.1E-06	--	--
Benzo(a)anthracene	0.047	--	--	1.37	3.4E-08
Benzo(a)pyrene	0.040	--	--	0.137	2.9E-07
Benzo(b)fluoranthene	0.049	--	--	1.37	3.6E-08
Benzo(ghi)perylene ^c	0.057	2,400	2.4E-05	--	--
Benzo(k)fluoranthene	0.018	--	--	13.7	1.3E-09
Chrysene	0.056	--	--	137	4.1E-10
Dibenz(a,h)anthracene	0.029	--	--	0.137	2.1E-07
Fluoranthene	0.086	3,200	2.7E-05	--	--
Fluorene	0.018	3,200	5.6E-06	--	--
Indeno(1,2,3-cd)pyrene	0.067	--	--	1.37	4.9E-08
Phenanthrene ^c	0.094	24,000	3.9E-06	--	--
Pyrene	0.093	2,400	3.9E-05	--	--
Totals					
Cumulative Hazard Quotient:			1.9E-03		
Cumulative Excess Cancer Risk:			6.2E-07		

Notes:

^a = From WCH (2012).^b = Value obtained from the 100-N Area RDR/RAWP (DOE-RL 2006b) or *Washington Administrative Code* (WAC) 173-340-740(Method B, 1996, unless otherwise noted.^c = Toxicity data for these chemicals are not available. The cleanup levels are based on use of surrogate chemicals.

benzo(g,h,i)perylene surrogate: pyrene

phenanthrene surrogate: anthracene

-- = not applicable

RAG = remedial action goal

CONCLUSION:

The calculations in Table 1 demonstrate that the 100-N-25 waste site meets the requirements for the direct contact hazard quotients and carcinogenic (excess cancer) risk, respectively, as identified in the RDR/RAWP (DOE-RL 2006b) and SAP (DOE-RL 2006a). The direct contact hazard quotients and carcinogenic (excess cancer) risk calculations are for use in the RSVP for this site.

CALCULATION COVER SHEETProject Title: 100-N Field Remediation Job No. 14655Area: 100-NDiscipline: Environmental *Calculation No: 0100N-CA-V0153Subject: 100-N-25 Hazard Quotient and Carcinogenic Risk Calculation for Protection of GroundwaterComputer Program: Excel Program No: Excel 2003

The attached calculations have been generated to document compliance with established cleanup levels. These calculations should be used in conjunction with other relevant documents in the administrative record.

Committed Calculation ☒Preliminary ☐Superseded ☐Voided ☐

Rev.	Sheet Numbers	Originator	Checker	Reviewer	Approval	Date
0	Cover = 1 Sheets = 3 Total = 4	J. D. Skoglie <i>[Signature]</i>	C. H. Dobie <i>[Signature]</i>	N. K. Schiffern <i>[Signature]</i>	D. F. Obenauer <i>[Signature]</i>	12/20/12

SUMMARY OF REVISION

Washington Closure Hanford, Inc.

CALCULATION SHEET

Originator:	J. D. Skoglie	Date:	10/15/12	Calc. No.:	0100N-CA-V0153	Rev.:	0
Project:	100-N Area Field Remediation	Job No:	14655	Checked:	C. H. Dobie	Date:	10/15/12
Subject:	100-N-25 Waste Site Hazard Quotient and Carcinogenic Risk Calculation for Protection of Groundwater					Sheet No. 1 of 3	

PURPOSE:

Provide documentation to support the calculation of the hazard quotient (HQ) and excess carcinogenic risk associated with soil contaminant levels compared to soil cleanup levels for protection of groundwater for the 100-N-25 waste site. In accordance with the remedial action goals (RAGs) in the remedial design report/remedial action work plan (RDR/RAWP) for the 100-N Area (DOE-RL 2006), the following criteria must be met:

- 1) An HQ of <1.0 for all individual noncarcinogens
- 2) A cumulative HQ of <1.0 for noncarcinogens
- 3) An excess cancer risk of <1 x 10⁻⁶ for individual carcinogens
- 4) A cumulative excess cancer risk of <1 x 10⁻⁵ for carcinogens.

GIVEN/REFERENCES:

- 1) BHI, 2005, *100 Area Analogous Sites RESRAD Evaluation*, Calculation No. 0100X-CA-V0050, Rev. 0, Bechtel Hanford, Inc., Richland, Washington.
- 2) DOE-RL, 2006, *Remedial Design Report/Remedial Action Work Plan for the 100-N Area*, DOE/RL-2005-93, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington.
- 3) WAC 173-340, "Model Toxics Control Act - Cleanup," *Washington Administrative Code*, 1996.
- 4) WCH, 2012, *Remaining Sites Verification Package for the 100-N-25, French Drain 1 Liquid Waste Site*, Attachment to Waste Site Reclassification Form 2012-079, Rev 0, Washington Closure Hanford, Inc., Richland, Washington.

SOLUTION:

- 1) Generate a HQ for each noncarcinogenic constituent detected above background in soil and with a K_d less than that required to show no migration to groundwater in 1,000 years using the RESRAD generic site model (BHI 2005).
- 2) Sum the HQs and compare this value to the cumulative HQ of <1.0.
- 3) Generate an excess cancer risk value for each carcinogenic constituent detected above background in soil and with a K_d less than that required to show no migration to groundwater in 1,000 years using the RESRAD generic site model (BHI 2005).
- 4) Sum the excess cancer risk value(s) and compare it to the cumulative cancer risk of <1 x 10⁻⁵.

Washington Closure Hanford, Inc.		CALCULATION SHEET			
Originator:	J. D. Skoglie	Date:	09/13/12	Calc. No.:	0100N-CA-V0153
Project:	100-N Area Field Remediation	Job No:	14655	Checked:	C. H. Dobie
Subject:	100-N-25 Waste Site Hazard Quotient and Carcinogenic Risk Calculation for Protection of Groundwater				Rev.: 0 Date: 09/13/12 Sheet No. 2 of 3

METHODOLOGY:

The 100-N-25 waste site is comprised of one decision unit for verification sampling, consisting of the excavation area. The protection of groundwater hazard quotient and carcinogenic risk calculations for the 100-N-25 waste site were conservatively calculated for the entire waste site using the statistical or maximum value for each analyte (WCH 2012). Based on the generic site RESRAD model (BHI 2005) and a vadose zone thickness of approximately 21 m (69 ft), a K_d of 3.6 or greater is required to show no predicted migration to groundwater in 1,000 years. Nitrogen in nitrate and nitrite requires HQ and risk calculations because they are detected above the Washington State or Hanford Site background value, and has a K_d of less than 3.6. Boron is included because it has a K_d of less than 3.6, and no Hanford background value has been established. All other site nonradionuclide COPCs were undetected, quantified below background levels, or have a K_d greater than or equal to 3.6. An example of the HQ and risk calculations for soil constituents with a potential impact to groundwater is presented below:

- 1) The hazard quotient is defined as the ratio of the dose of a substance obtained over a specified time (mg/kg/day) to a reference dose for the same substance derived over the same specified time (mg/kg/day). The hazard quotient can also be calculated as the ratio of the concentration in soil (maximum or statistical value) (mg/kg) to the soil RAG (mg/kg) for protection of groundwater, where the RAG is the groundwater cleanup level ($\mu\text{g/L}$) (calculated with, and related to the hazard quotient through, WAC 173-340-720 (3)(a)(ii)(A), (1996) $\times 100 \times 1 \text{ mg}/1000 \mu\text{g}$ (conversion factor). This is based on the "100 times rule" of WAC 173-340-740(3)(a)(ii) (A) (1996). For example, the statistical value for boron of 1.4 mg/kg, divided by the noncarcinogenic RAG value of 320 mg/kg is 4.4×10^{-3} . Comparing this value to the requirement of <1.0 , this criterion is met.
- 2) After the HQ calculation is completed for the appropriate analytes, the cumulative HQ can be obtained by summing the individual values. (To avoid errors due to intermediate rounding, the individual HQ values prior to rounding are used for this calculation.) The cumulative HQ for the 100-N-25 waste site is 1.1×10^{-1} . Comparing this value to the requirement of <1.0 , this criterion is met.
- 3) To calculate the excess cancer risk, the maximum or statistical value is divided by the carcinogenic RAG value, and then multiplied by 1×10^{-6} . There were not any constituents in this calculation that had a carcinogenic RAG associated with it. Therefore, the requirement of $<1 \times 10^{-6}$ is met. Furthermore, the criterion for cumulative excess cancer risk for carcinogens is also met.
- 4) The soil cleanup RAGs for protection of groundwater are based on the "100 times" provision in WAC 173-340-740(3)(a)(ii)(A). WAC 173-340-740(3)(a)(ii)(A) (1996) provides the "100 times rule" but also states "unless it can be demonstrated that a higher soil concentration is protective of ground water at the site." When the "100 times rule" values are exceeded, RESRAD was used to demonstrate that higher soil concentrations may be protective of groundwater.

Washington Closure Hanford, Inc.

CALCULATION SHEET

Originator:	J. D. Skoglie	Date:	10/15/12	Calc. No.:	0100N-CA-V0153	Rev.:	0
Project:	100-N Area Field Remediation	Job No.:	14655	Checked:	C. H. Dobie <i>CH</i>	Date:	10/15/12
Subject:	100-N-25 Waste Site Hazard Quotient and Carcinogenic Risk Calculation for Protection of Groundwater					Sheet No. 3 of 3	

RESULTS:

- 1) List individual noncarcinogens and corresponding HQs >1.0: None
- 2) List the cumulative noncarcinogenic HQ >1.0: None
- 3) List individual carcinogens and corresponding excess cancer risk >1 x 10⁻⁶: None
- 4) List the cumulative excess cancer risk for carcinogens >1 x 10⁻⁵: None.

Table 1 shows the results of the calculations.

Table 1. Hazard Quotient and Excess Cancer Risk Results for the 100-N-25 Waste Site.

Contaminants of Potential Concern	Maximum or Statistical Value ^a (mg/kg)	Noncarcinogen RAG ^b (mg/kg)	Hazard Quotient	Carcinogen RAG ^b (mg/kg)	Carcinogen Risk
Metals					
Boron	1.4	320	4.4E-03	--	--
Anions					
Nitrogen in Nitrate and Nitrite	103	1,000	1.0E-01	--	--
Totals					
Cumulative Hazard Quotient:			1.1E-01		
Cumulative Excess Cancer Risk:					0.0E+00

Notes:

^a = From WCH (2012).^b = Value obtained from the Cleanup Levels and Risk Calculations (CLARC) database using Groundwater, Method B, results and the "100 times" model.

-- = not applicable

RAG = remedial action goal

CONCLUSION:

This calculation demonstrates that the 100-N-25 waste site meets the requirements for the hazard quotients and excess carcinogenic risk for protection of groundwater as identified in the RDR/RAWP (DOE-RL 2006).

APPENDIX C
DATA QUALITY ASSESSMENT

APPENDIX C

DATA QUALITY ASSESSMENT

VERIFICATION SAMPLING

A data quality assessment (DQA) was performed to compare the verification sampling approach and resulting analytical data with the sampling and data requirements specified in the site-specific sample design (WCH 2012b). This DQA was performed in accordance with site-specific data quality objectives found in the *100-N Area Sampling and Analysis Plan for CERCLA Waste Sites* (100-N Area SAP) (DOE-RL 2006).

A review of the sample design (WCH 2012b), the field logbook (WCH 2012a), and applicable analytical data packages has been performed as part of this DQA. All samples were collected and analyzed per the sample design. In addition, ion chromatography (IC) anions analysis, by EPA method 9056, was also requested. IC anions are not contaminants of potential concern (COPCs) for 100-N-25 waste site.

To ensure quality data, the SAP data assurance requirements and the data validation procedures for chemical analysis (BHI 2000) are used as appropriate. This review involves evaluation of the data to determine if they are of the right type, quality, and quantity to support the intended use (i.e., closeout decisions). The DQA completes the data life cycle (i.e., planning, implementation, and assessment) that was initiated by the data quality objectives process (EPA 2006).

Verification sample data collected at the 100-N-25 waste site were provided by the laboratory in sample delivery group (SDG) J01572. SDG J01572 was submitted for third-party validation. No major deficiencies were identified in the analytical data set. Minor deficiencies are discussed for the 100-N-25 data set, as follows below. If no comments are made about a specific analysis, it should be assumed that no deficiencies affecting the quality of the data were found.

SDG J01572

This SDG comprises 13 statistical verification samples (J1PVN7 through J1PVN9, J1PVP0 through J1PVP9) from the 100-N-25 excavation. This SDG includes a field duplicate pair (J1PVP0/J1PVP9). These samples were analyzed for inductively coupled plasma (ICP) metals, mercury, nitrate/nitrite, IC anions, polycyclic aromatic hydrocarbons (PAH), and total petroleum hydrocarbons (TPH). SDG J01572 was submitted for third-party validation. In addition, one equipment blank (J1PVR0) was analyzed for ICP metals and mercury. Minor deficiencies are as follows:

In the ICP metals analysis, the chromium and zinc were detected at low levels in the method blank (MB). Significantly higher concentrations of chromium and zinc were detected in the field samples, and their results are not comparable to the concentrations observed in the MB. However, the chromium and zinc results in the field equipment blank sample (J1PVR0) are

comparable to the equipment blank and have been qualified as undetected and estimated with “UJ” flags by third-party validation. Estimated data are usable for decision-making purposes.

In the ICP metals analysis, all silicon results were considered estimates and flagged “J” by third-party validation due to a laboratory control sample (LCS) result below the quality control (QC) limits at 16%. Estimated data are usable for decision-making purposes.

In the ICP metals analysis, the relative percent differences (RPDs) for calcium and silicon are above the project QC limit of 30%, at 83% and 39%, respectively. In addition, the RPD for silicon is above the project QC limit of 30%, at 39%. The associated sample results are considered estimates and were flagged “J” by the third-party validation. Estimated data are usable for decision-making purposes.

In the ICP metals analysis, the matrix spike (MS) recoveries were out of project acceptance criteria for four analytes (aluminum, antimony, iron, and silicon). For aluminum and iron, the spiking concentration was insignificant compared to the native concentration in the sample from which the MS was prepared. The deficiency in the MS is a reflection of the analytical variability of the native concentration rather than a measure of the recovery from the sample. Antimony and silicon did not have mismatched spike and native concentrations in the original MS. The original MS recoveries for antimony and silicon were 42% and -10%. All antimony and silicon data for SDG J01572 were considered estimates and flagged “J” by third-party validation due to the MS recoveries outside the limits. Estimated data are usable for decision-making purposes.

FIELD QUALITY ASSURANCE/QUALITY CONTROL

Relative percent difference evaluations of main sample(s) versus the laboratory duplicate(s) are routinely performed and reported by the laboratory. Any deficiencies in those calculations are reported by SDG in the previous sections.

Field quality assurance (QA)/QC measures are used to assess potential sources of error and cross contamination of samples that could bias results. The field QA/QC sample, listed in the field logbook (WCH 2012a), is shown in Table C-1. The main and QA/QC sample results are presented in Appendix B.

Table C-1. Field Quality Assurance/Quality Control Samples.

Sample Area	Main Sample	Duplicate Sample
Excavation	J1PVP0	J1PVP9

Field duplicate samples are collected to provide a relative measure of the degree of local heterogeneity in the sampling medium, unlike laboratory duplicates that are used to evaluate precision in the analytical process. The field duplicates are evaluated by computing the RPD of the sample/duplicate pair(s) for each COPC. Relative percent differences are not calculated for analytes that are not detected in both the main and duplicate sample at more than five times the

target detection limit (TDL). Relative percent differences of analytes detected at low concentrations (less than five times the detection limit) are not considered to be indicative of the analytical system performance. The calculation brief in Appendix B provides details on duplicate pair evaluation and RPD calculation.

None of the RPD calculated for the field duplicate sample are above the acceptance criteria of 30%. A secondary check of the data variability is used when one or both of the samples being evaluated (main and duplicate) is less than five times the TDL, including undetected analytes. In these cases, a control limit of ± 2 times the TDL is used (Appendix B) to indicate that a visual check of the data is required by the reviewer. No sample results required this check. A visual inspection of all of the data is also performed. No additional major or minor deficiencies are noted. The data are usable for decision-making purposes.

Summary

Limited, random, or sample matrix-specific influenced batch QC issues such as those discussed above are a potential for any analysis. The number and types seen in these data sets are within expectations for the matrix types and analyses performed. The DQA review of the 100-N-25 waste site verification sampling data found that the analytical results are accurate within the standard errors associated with the analytical methods, sampling, and sample handling. The DQA review for the 100-N-25 waste site concludes that the reviewed data are of the right type, quality, and quantity to support the intended use. The analytical data were found acceptable for decision-making purposes.

The verification sample analytical data are stored in the Environmental Restoration project-specific database prior to being submitted for inclusion in the Hanford Environmental Information System database. The verification sample analytical data are also summarized in Appendix B.

REFERENCES

- BHI, 2000, *Data Validation Procedure for Chemical Analysis*, BHI-01435, Rev. 0, Bechtel Hanford, Inc., Richland, Washington.
- DOE-RL, 2006, *100-N Area Sampling and Analysis Plan for CERCLA Waste Sites*, DOE/RL-2005-92, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington.
- EPA, 2006, *Guidance on Systematic Planning using the Data Quality Objectives Process*, EPA QA/G-4, U.S. Environmental Protection Agency, Office of Environmental Information, Washington, D.C.
- WCH, 2012a, *100-N Field Remediation Sampling*, Logbook EL-1652-06, pp. 67-69, Washington Closure Hanford, Richland, Washington.

WCH, 2012b, *Work Instruction for Verification Sampling of the 100-N-25, French Drain 1 Liquid Waste Site*, 0100N-WI-G0046, Rev. 0, Washington Closure Hanford, Richland, Washington.